



## **ADDENDUM # 2**

Project Name: Retaining Wall Replacement

Location: Currituck County Veterans Memorial Park

Date: June 16, 2016

**BIDDERS MUST ACKNOWLEDGE THE RECEIPT OF ADDENDUM # 1 ON THE ATTACHED REVISED BID FORM.**

The following clarifications/changes are made to the Contract Documents:

This addendum also addresses requests for clarification from the Pre-Bid Conference held June 8, 2016 on the site.

1. Please use the attached revised plan sheets S-1 to S-3 with revision Note A dated 6-15-16 for bidding this project.
2. Please use the attached revised bid form. Replacement of the asphalt parking removed during retaining wall construction will be bid as a unit price and the owner may choose to install. There is an estimated 20' x 45' wide section of asphalt parking to be removed. The parking lot shall be saw cut in a straight line and all asphalt and up to 4" of gravel base (if present) shall be removed and replaced with top soil and seeded. The unit price bid for asphalt replacement shall be installed in accordance with the plans.

End of Addendum # 2

Eric T. Weatherly, PE, County Engineer  
County of Currituck, NC