

**Corolla Horse Fence Restoration Project  
Addendum 1**

The following items are included as Addendum 1 to the Horse Fence Restoration Project:

1. Height of two pedestrian accesses:
  - a. West of North Access Beach Rd: 5 ft above existing grade
  - b. East of North Access Beach Rd: To remain at current height (~ 5ft). The existing posts for this access shall remain. The horizontal rails shall be replaced.
    - i. See attached plan sheet for location
    - ii. Price for this item to be included in the first Lump Sum item on the Bid Form ('Restoration of 650 feet of wood fencing along east side of North Access Beach Road').
2. Replace 20 ft section of concrete sidewalk along pedestrian access (west of North Beach Access Rd).
  - a. Dimensions:
    - i. Length: 20 ft
    - ii. Width: 6 ft
    - iii. Thickness: 6"
  - b. Concrete strength: 3,000 psi
  - c. Replace from the existing expansion joint south of the access entrance to the existing expansion joint north of the entrance.
  - d. New expansion joints shall be replaced at existing locations. Control joints shall be placed every 5 ft.
  - e. Broom finish surface perpendicular to path of travel.
  - f. 40 ft x 2 ft of river rock (2" – 4") shall be placed between sidewalk and pavement (erosion control).
  - g. This item will be an alternate (option) item and executed at the County's discretion. Price for this item to be added to the Bid Form and should not be included with the 'GRAND TOTAL BID AMOUNT'.
3. Exposed cabling running along existing wooden fence shall be cut, removed and disposed of where possible.
  - a. Price for this item to be included in the first Lump Sum item on the Bid Form ('Restoration of 650 feet of wood fencing along east side of North Access Beach Road').
4. Fence grade transition near beach access ramp.
  - a. See detail sheet attached for details.
5. Remove two exposed broken pilings between toe of dune and beach access gate.
  - a. See attached plan sheet for piling locations.
  - b. Price for this item to be included in the fifth Lump Sum item on the Bid Form ('Removal and replacement of cables and hardware along round pilings').
6. The 16 ft beach gate is no longer a requirement for the project.
7. Replace existing 4 ft cattle gate east of beach access gate with new 4 ft, galvanized cattle gate.

- a. Price for this item will replace the '16 ft beach gate' in the fourth Lump Sum item on the Bid Form ('Removal and replacement of two access gates').