

POPLAR BRANCH TOWNSHIP

THE FOLLOWING PERMITS ARE REQUIRED PRIOR
PERMIT
SEDIMENTATION AND EROSION CONTROL PERMIT
STORMWATER MANAGEMENT PERMIT
WATERLINE EXTENSION AUTHORIZATION TO CONSTRU
WASTEWATER COLLECTION SYSTEM PERMIT
WETLAND PERMIT
CURRITUCK COUNTY PRELIMINARY PLAT & USE PERI
CURRITUCK COUNTY CONSTRUCTION AUTHORIZATIO

CONSTRUCTION DRAWINGS FOR COROLLA BOAT CLUB - PHASE 1 A 6 LOT SUBDIVISION DEVELOPMENT

MONTERAY SHORES PHASE 10 CURRITUCK COUNTY

Sheet List Table				
Sheet Number	Sheet Title			
1	COVER SHEET, DEVELOPMENT NOTES & SITE LOCATION			
2	EXISTING CONDITIONS & SITE FEATURES MAP			
3	DEVELOPMENT OVERVIEW PLAN			
4	GRADING, DRAINAGE & STORMWATER MANAGEMENT			
5	EROSION & SEDIMENT CONTROL PLAN AND SEQUENCE			
6	WATER MAIN EXTENSION AND WASTEWATER COLLECTION PLAN			
7	LANDSCAPING, LIGHTING & SIGNAGE PLAN			
8	VIRGINIA LANE PLAN & PROFILE (0+00 - 8+31)			
9	ROADWAY, DRAINAGE & MISC. CONSTRUCTION DETAILS			
10	ROADWAY, SIDEWALK & MISC. CONSTRUCTION DETAILS			
11	EROSION AND SEDIMENT CONTROL NOTES & DETAILS			
12	NCG01 – GROUND STABILIZATION & MATERIALS HANDLING			
13	NCG01 – SELF INSPECTION, RECORDKEEPING & REPORTING			
14	WASTEWATER LIFT STATION CONSTRUCTION DETAILS			
15	WASTEWATER COLLECTION TYP. CONSTRUCTION DETAILS			
16	WASTEWATER COLLECTION TYP. CONSTRUCTION DETAILS			

R TO F	PROJECT CONSTRUCTION:		
	AGENCY	REFERENCE NUMBER	DATE OF ISSUANCE
a a general de la constante de	N.C.D.E.Q DIVISION OF LAND RESOURCES		
	N.C.D.E.Q - DIVISION OF LAND RESOURCES		
ICT	N.C.D.E.Q - PUBLIC WATER SUPPLY		
	N.C.D.E.Q - DIVISION OF WATER RESOURCES		
	U.S.A.C.O.E.		
ΜΙΤ	CURRITUCK COUNTY BOARD OF COMMISSIONERS		
N	CURRITUCK COUNTY PLANNING STAFF		

STORMWATER CERTIFICATE
I,, OWNER/AGENT HEREBY CERTIFY THE INFOR INCLUDED ON THIS AND ATTACHED PAGES IS TRUE AND CORRECT TO T OF MY KNOWLEDGE.
ON THE PLAN ENTITLED, <u>COROLLA BOAT CLUB – PHASE 1 – CONSTRU</u> <u>DRAWINGS – GRADING, DRAINAGE AND STORMWATER MANAGEMENT PLA</u> STORMWATER DRAINAGE IMPROVEMENTS SHALL BE INSTALLED ACCORDIN THESE PLANS AND SPECIFICATIONS AND APPROVED BY CURRITUCK COL YEARLY INSPECTIONS ARE REQUIRED AS PART OF THE STORMWATER PL OWNER IS RESPONSIBLE FOR ALL MAINTENANCE REQUIRED. CURRITUCK ASSUMES NO RESPONSIBILITY FOR THE DESIGN, MAINTENANCE, OR PERI OF THE STORMWATER IMPROVEMENTS.
DATE OWNER/AGENT

















GENERAL LANDSCAPING AND BUFFERING NOTES: 1. STREET TREES:

MBL

2°°_____°° _____°

- STREET TREES SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 6.2.1.L OF THE CURRITUCK UDO. • TREES SHALL BE PLANTED ALONG EACH SIDE OF ROADWAYS AS GENERALLY
- SPECIFIED ON THE LANDSCAPE PLANS. • EXISTING TREES RETAINED IN THE VICINITY MAY BE CREDITED AS STREET TREES.
- TREES SHALL BE PLANTED 35'± FROM CENTERLINE OF THE ROAD

-0-

- TREES SHALL BE <u>CANOPY</u> TYPE PLANTED A MAXIMUM OF 50' O/C.
 SEE TREE SPECIES AND PLANTING NOTE BELOW
- 4. OPEN SPACE VEGETATION: OPEN SPACE VEGETATION REQUIREMENTS ARE ACHIEVED THROUGH THE PRESERVATION OF THE EXISTING TREES ON THE PROPERTY TO THE MAXIMUM EXTENT PRACTICABLE. 5. HERITAGE TREES:
- A TOTAL OF (5) HERITAGE TREES HAVE BEEN IDENTIFIED WITHIN THE PROJECT AREA. ALL HERITAGE TREES ARE INTENDED TO REMAIN AND BE PROTECTED DURING CONSTRUCTION. (SEE "HERITAGE TREE PROTECTION FENCING" DETAIL THIS SHEET.) ANY HERITAGE TREES THAT ARE LOTS SHALL BE MITIGATED PURSUANT TO THE U.D.O. 6. TREE SPECIES AND PLANTING:
- TREES SHALL BE INSTALLED IN ACCORDANCE WITH THE PLANTING STANDARDS SPECIFIED IN SECTION 3.5 OF THE CURRITUCK COUNTY ADMINISTRATIVE MANUAL. <u>CANOPY</u> AND <u>UNDERSTORY</u> TREE SPECIES SHALL BE OF THOSE LISTED UNDER "TABLE 3.4.6: RECOMMENDED PLANTINGS" IN THE SAME MANUAL.
- TREE SPECIES SHALL BE DIVERSE. A MINIMUM OF (4) DIFFERENT SPECIES OF CANOPY TREES SHALL BE INSTALLED IN ROUGHLY EQUAL PROPORTIONS.
- AT INSTALLATION, <u>CANOPY</u> TREES SHALL HAVE A MINIMUM CALIPER OF <u>2 INCHES</u> MEASURED AT 6 INCHES. ABOVE GRADE. EIGHT FOOT HIGH TREES MAY BE PLANTED MATERIALS SHALL BE OF HIGH-QUALITY NURSERY GRADE
 THE USE OF NATIVE, DROUGHT TOLERANT TREES IS ENCOURAGED.
- A REPUTABLE LANDSCAPE CONTRACTOR OR SUPPLIER SHALL PREPARE AN ITEMIZED SCHEDULE OF TREES TO BE INSTALLED IN ACCORDANCE WITH THIS LANDSCAPE PLAN. THIS SCHEDULE OF THELES TO BE INSTALLED IN ACCORDANCE WITH THIS LANDSCAPE PLAN. THIS SCHEDULE SHALL BE REVIEWED BY CURRITUCK COUNTY AND THE ENGINEER TO DETERMINE COMPLIANCE BEFORE ORDERING AND INSTALLATION. ALTERNATE TREES AND SPECIFICATIONS MAY BE PRESENTED FOR REVIEW AND APPROVAL.



 \angle







Image: State of the
Image: Solution of the second seco





GENERAL PROJECT NOTES:

PROJECT NAME: COROLLA BOAT CLUB - PHASE 1 POPLAR BRANCH, CURRITUCK COUNTY, NORTH CAROLINA 2. APPLICANT: OUTER BANKS VENTURES, INC. P.O. BOX 549 COROLLA, NC 27927

3. PROJECT DESCRIPTION: 6 LOT SUBDIVISION 4. NEAREST RECEIVING STREAM: SANDERS BAY - INDEX NUMBER: 30-1-11 5. STREAM CLASSIFICATION: SC - PASQUOTANK RIVER BASIN 6. PROJECT AREA TABULATION TOTAL PROPERTY AREA : 36 AC. 12.0 AC. TOTAL PROPOSED DISTURBED AREA

AREA CALCULATION NOTE: All areas have been calculated utilizing properties within the Autocad software. MATERIAL BALANCE NOTE All excavated material occurring during the course of construction shall remain on-site for roadway

construction and lot grading. See <u>SCHEDULE OF LAND DISTURBING ACTIVITIES provided on</u> Sheet 5 of this set for an estimated cut fill material balance for the project. WETLAND NOTE:

No 404 jurisdictional wetlands have been identified on the property STABILIZATION NOTE:

The angle of graded slopes and fills shall be no greater than the angle that can be retained by

vegetative cover or other adequate erosion control devices or structures. In any event, all disturbed areas left exposed will, WITHIN 14 CALENDAR DAYS OF COMPLETION of any phase of grading, be planted or otherwise provided with temporary or permanent ground cover devices, or structures sufficient to restrain erosion. Additionally, certain critical areas as identified on the plan, such as, but not limited to, perimeter dikes

swales, slopes steeper than 3:1, and areas located within High Quailty Water Zones, must be temporarily or permanetly stabilzed WITHIN 7 CALENDAR DAYS OF COMPLETION of any phase of grading in these areas. A permanent ground cover for all disturbed areas must be provided WITHIN 15 WORKING DAYS OF 90 CALENDAR DAYS (whichever is shorter) following completion of construction or development.

SEDIMENTATION AND EROSION CONTROL NOTES:

NOT TO SCALE

A. NARRATIVE AND SITE DATA COROLLA BOAT CLUB - PHASE 1 IS A MIXED USE DEVELOPMENT SLATED FOR CONSTRUCTION ON A VACANT TRACT OF LAND LOCATED WEST OF NC HWY 12 ALONG THE SOUTH SIDE OF MALIA DR IN THE COROLLA, CURRITUCK COUNTY. THE DEVELOPMENT IS ALSO KNOWN AS PHASE 10 OF THE MONTERAY SHORES PUD AND INCLUDES 1 COMMERCIAL LOT AND 5 RESIDENTIAL SINGLE FAMILY HOME LOTS. THE SUBDIVISION IS SERVED BY PROPOSED ROADWAY, DRAINAGE, UTILITY AND AMENITY IMPROVEMENTS. THE SITE'S EXISTING TOPOGRAPHY IS GENERALLY FLAT, WITH SLOPES RANGING BETWEEN 0-1% AND ELEVATIONS RANGING FROM 10 FT MSL TO BELOW 1 FT MSL. THE PROPERTY IS BOUNDED TO THE NORTH BY MALIA DR. TO THE EAST AND SOUTH BY EXISTING COMMERCIAL DEVELOPMENT AND TO THE WEST BY SANDERS BAY, THE PROPERTY IS CURRENTLY VACANT SURROUNDING DEVELOPMENT IS PRIMARILY COMMERCIAL. APPROX. 21 ACRES OF CAMA AND 404 JURISDICTIONAL WETLANDS EXISTT BETWEEN THE SOUTHEASTERN UPLAND AREAS AND THE BAY. ON-SITE DRAINAGE IS LIMITED TO AN EXISTING CULVERT EXTENDING FROM MALIA DR. TO AN EXISTING POND LOCATED ON THE PROPERTY, THE EXISTING CULVERT SERVICES AS A DRAINAGE OUTLET TO SURROUNDING COMMERCIAL DEVELOPMENTS PURSUANT TO THE USDA SOIL SURVEY MANUAL OF CURRITUCK COUNTY, SITE SOILS ARE PRIMARILY COMPOSED OF OSIER FINE SAND ACROSS THE DEVELOPABLE UPLAND AREA AND CURRITUCK MUCKY PEAT ACROSS THE WETLANDS.

CONSTRUCTION SEQUENCE SCHEDULE

CONSTRUCTION ACTIVITY Construction Access- Construction entrance, construction routes, equipment parking areas

Sediment Traps & Barriers Basin traps, sediment fences, & outlet protection

Runoff Control-Diversions, perimeter dikes, water bars, and outlet protection

Runoff Conveyance System-Stabiles stream banks, storm drains, channels, Inlet & outlet protection, slope runoff conveyance system with drains

and Clearing & Grading-Site preparation- cutting, filling & grading, sediment traps, barriers, diversions, drains, surface roughening

Surface Stabilization-Temporary & permanent seeding, mulching, sodding, rip rap.

Building Construction-Buildings, utilities, paving. Landscaping & Final Stabilization-

Topsoiling, trees & shrubs, permanent seeding, mulching, sodding, rip rap

SCHEDULE CONSIDERATION First land-disturbing activity-Stabilize bare areas immediately with gravel & temporary vegetation as construction takes place.

Install principal basins after construction site is accessed. Install additional traps and barriers as needed during grading.

Install key practices after principal sediments traps and before land grading. Install additional runoff-control conveyance measures during grading.

Where necessary, stabilize stream banks as early as possible. Install principal runoff-control measures. Install remainder materials into fill slopes. of system after grading.

Begin major clearing and grading after principal & key runoff—control measures area installed. Clear borrow & disposal areas as needed. Install additional control measures as grading progresses. Mark trees & buffer areas for preservation.

Apply temporary or permanent disturbed areas where work is delayed or complete.

Install necessary erosion & sedimentation control practices as work takes place.

Stabilize all open areas, including borrow & spoil areas. Remove & stabilize all temporary control measures.

control plan





ROLLED LINER CONNECTION DETAIL

NOT TO SCALE



ROLLED EROSION CONTROL MATTING DETAIL NO SCALE LOCATION AS NOTED ON PLAN

ROLLED EROSION CONTROL MATTING (R.E.C.M.) SPECIFICATIONS: 1. All areas identified on these plans as requiring an erosion control matting shall be lined with a protective covering to minimize erosion and protect seed until

- permanent vegetation is established. Covering shall be composed of a bio or photo degradable material to minimize long term environmental impacts.
- 3. Mulching with straw or other organic materials can be utilized only when it will not impede the establishment of permanent vegetation. Mulches must be properly anchored which may be difficult in some environments. An example is straw mulch with jute netting stapled or pinned in place.
- 4. Pre-manufactured rolled erosion control products (RECP) are highly recommended for this application. RECP's shall be installed according to manufacturer specifications for channel linings. An example is a woven straw or wooden fiber Excelsior matting.



INSPECT AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (2" OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE DEBRIS FROM MESH AND REPLACE STONES AS NEEDED. REMOVE ONCE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED.



CONSTRUCTION ENTRANCE NO SCALE LOCATION AS NOTED ON PLAN

CONSTRUCTION ENTRANCE SPECIFICATIONS 1. Length - minimum of 50' (*30' for single residence lot). 2. Width -12' minimum, should be flared at the existing road to provide a turning radius. 3. Geotextile fabric (filter cloth) shall be placed over the existing ground prior to placing stone. **The plan approval authority may not require single family residences to use geotextile. 4. Stone - crushed aggregate (2" to 3") or reclaimed or recycled concrete equivalent shall be placed at least 6" deep over the length and width of the entrance. 5. Surface Water - all surface water flowing to or diverted toward construction entrances shall be piped through the entrance, maintaining positive drainage. Pipe installed through the stabilized construction entrance shall be protected with a mountable berm with 5:1 slopes and a minimum of 6" of stone over the pipe. Pipe has to be sized according to the drainage. When the SCE is located at a high spot and has no drainage to convey a pipe will not be necessary. Pipe should be sized according to the amount of runoff to be conveyed. A 6" minimum will be required. 6. Location - A stabilized construction entrance shall be located at every point where construction traffic enters or leaves a construction site. Vehicles leaving the site must travel over the entire length of the stabilized construction entrance.

LAND GRADING CONSTRUCTION SPECIFICATIONS

1. Construct & maintain all erosion & sedimentation control practices & measures in accordance with the approved sedimentation control plan and construction schedule. 2. Remove good topsoil from areas to be graded and filled, and preserve it for use in finishing the grading of all critical areas.

layers as required to reduce erosion, slippage, settlement, or other related problems. 7. Do not incorporate frozen material or soft, mucky, or highly compressible

8. Do not place fill on a frozen foundation, due to possible subsidence and slippage. 9. Keep diversions and other water conveyance measures free of sediment during all

10. Handle seeps or springs encountered during construction in accordance with approved methods.

11. Following completion of any phase of grading, provide a groundcover (temporary stabilization measures immediately on all or permanent) on all exposed slopes within 14 calendar days, or 7 calendar days in critical areas identified on the plan; and, a permanent groundcover for all disturbed areas within 15 working days or 90 calendar days (whichever is shorter) following completion of construction or development.

phases of development.

MAINTENANCE Periodically check all graded areas & the supporting erosion & sedimentation control practices, especially after heavy rainfalls. Promptly remove all sediment from diversions and other water-disposal practices. If washouts or breaks occur, repair them immediately. Prompt maintenance of small-eroded areas before they become significant gullies is an essential part of an effective erosion & sedimentation

3. Scarify areas to be topsoiled to a minimum depth of 2 inches before placing

4. Clear & grub areas to be filled to remove trees, vegetation, roots, or other objectionable material that would affect the planned stability of fill. 5. Ensure that fill material is free of brush, rubbish, rocks, logs, stumps, building

debris, and other materials inappropriate for constructing stable fills. 6. Place all fill in layers not to exceed 9 inches in thickness, and compact the

12. Provide adequate protection from erosion for all topsoil stockpiles, borrow areas, and spoil areas.

PERMANENT SEEDING The purpose of permanent seeding is to reduce erosion and decrease sediment yield from disturbed areas, and to permanently stabilize such areas in a manner that is economical, adapts to site conditions, and allows

selection of the most appropriate plant materials. These areas must be seeded or planted within 15 working days or 90 calendar days after final grade is reached, unless temporary stabilization is applied.

PERMANENT SEEDING SPECIFICATIONS Seeding Recommendations for Summer SEEDING DATES - April to July

SEEDING MIXTURE

Species Rate Common bermudagrass 10/1,000 sf (sprigs) 1-2 lb/1,000 sf (seed)

SOD (See Sodding Notes) Seeding Recommendations for Early Fall through Early Spring SEEDING DATES - August to March (early fall and spring recommended)

Rate Species Kentucky 31 Tall Fescue 6 lb/1,000 sf (broadcast seed)

SEEDING NOTES-. Sprig or sod. Moisture is essential during initial establishment. Sod must be kept watered for 2-3weeks, but can be planted earlier or later than sprigs.

Soil Amendments-It is highly recommended that soils be tested and amended as found necessary. If a sois are not tested follow these recommendations: Apply 3,000 lb/acre of ground agricultural limestone and 500 lb/acre of 10-10-10 starter fertilizer, or 50 lb/acre nitrogen from turf-type

slow-release fertilizer. Add 25-50 lb/acre nitrogen at 2-3 week intervals through midsummer.

Plant sprigs in furrows with a tractor-drawn transplanter, or broadcast by hand. (Not recommended for Tall Fescue)

Furrows should be 4-6 inches deep and 2 feet apart. Place sprigs about 2 ft. apart in a row with one end at or above ground level.

Broadcast at rates shown above, and press sprigs into the top 1/2-2 inches of soil with a disk set straight so that sprigs are not brought back toward the surface.

Do not mulch Bermuda Grass. For Tall Fesuce seed, apply 4,000-lb/acre straw. Anchor straw by tacking with asphalt, netting, or a mulch-anchoring tool. A disk with blades set nearly straight can be used as a mulch-anchoring tool.

Maintenance-

Water as needed. Mow bermuda to 3/4 to 1-inch height and tall fescue to 2.5 - 3.5 inch height. Topdress bermuda with 40 lb/acre nitrogen in April, 50 Ib in May, 50 lb in June, 50 lb in July, and 25 lb in August. Top dress tall fescue in mid September, again in November and February with turf-grade 3-1-2 or 4-1-2 ratio turf-grade fertilizer. Fertilize with 1 lb of actual nitrogen per 1,000 sf. Do not fertilze tall fescue between Mid March and Early

July hours of the second

MAX AT CENTER

FILTER





NCDOT #5 OR #57 WASHED STON AVERAGE HEIGHT OF 16" ABOVE GRADE SIDE SLOPE AT 2:1(H:V)

MIN

SECTION VIEW TEMPORARY STONE CHECK DAM CONSTRUCTION NOT TO SCALE LOCATIONS AS NOTED ON PLAN TEMPORARY STONE CHECK DAM CONSTRUCTION SPECIFICATIONS: . CLEAR, GRUB, AND STRIP THE AREA UNDER THE EMBANKMENT OF ALL VEGETATION AND ROOT MAT. REMOVE ALL SURFACE SOIL CONTAINING HIGH AMOUNTS OF ORGANIC MATTER AND STOCKPILE OR DISPOSAL OF IT PROPERLY. HAUL ALL OBJECTIONABLE MATERIAL TO THE DESIGNATED DISPOSAL AREA.

FRONT VIEW

- 1.5' ----

2" OF #5 OR #57 STONE

9" FREEBOARD MIN.

PRES 9" FREEBOARD MIN

CLASS B

RIP RAP

2. PLACE STONE TO THE LINES AND DIMENSIONS SHOWN IN THE PLAN ON A FILTER FABRIC FOUNDATION. 3. KEEP THE CENTER STONE SECTION AT LEAST 9 INCHES BELOW NATURAL GROUND LEVEL WHERE THE DAM ABUTS

THE CHANNEL BANKS. 4. EXTEND STONE AT LEAST 1.5 FEET BEYOND THE DITCH BANK TO KEEP WATER FROM CUTTING AROUND THE ENDS OF THE CHECK DAM.

5. ALL CUT AND FILL SLOPES SHOULD BE 2:1 OR FLATTER.

SLAND SIG

MAX AT CENTER

6. PROTECT THE CHANNEL AFTER THE LOWEST CHECK DAM FROM HEAVY FLOW THAT COULD CAUSE EROSION. 7. MATERIAL USED IN THE STONE SECTION SHOULD BE A WELL-GRADED MIXTURE OF STONE WITH A d50 SIZE OF 9 INCHES(CLASS B EROSION CONTROL STONE IS RECOMMENDED) AND A MAXIMUM STONE SIZE OF 14 INCHES. THE STONE MAY BE MACHINE PLACED AND THE SMALLER STONES WORKED INTO THE VOIDS OF THE LARGER STONES. THE STONE SHOULD BE HARD, ANGULAR, AND HIGHLY WEATHER-RESISTANT.

8. STABILIZE THE EMBANKMENT AND ALL DISTURBED AREAS ABOVE THE SEDIMENT POOL AND DOWNSTREAM FROM THE TRAP IMMEDIATELY AFTER CONSTRUCTION. 9. ENSURE THAT OTHER AREAS OF THE CHANNEL, SUCH AS CULVERT ENTRANCES BELOW THE CHECK DAMS, ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACES STONES.

MAINTENANCE OF TEMPORARY STONE CHECK DAMS: INSPECT CHECK DAMS AND CHANNELS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (12" OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. CLEAN OUT SEDIMENT, STRAW, LIMBS, OR OTHER DEBRIS WHEN NEEDED. REMOVE SEDIMENT ACCUMULATION BEHIND THE DAMS AS NEEDED TO PREVENT DAMAGE TO CHANNEL VEGETATION,

ALLOW THE CHANNEL TO DRAIN THROUGH THE STONE CHECK DAM, AND PREVENT LARGE FLOWS FROM CARRYING SEDIMENT OVER THE DAM. ADD STONES TO DAMS AS NEEDED TO MAINTAIN DESIGN HEIGHT AND CROSS SECTION.



GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

	Re	equired Ground Stabi	lization Timeframes	
Sit	te Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations	
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None	
(b)	High Quality Water (HQW) Zones	7	None	
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed	
(d)	Slopes 3:1 to 4:1	14	 -7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed 	
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zon -10 days for Falls Lake Watershed unles there is zero slope	
roui ract ctivi urfa	icable but in no case l ity. Temporary groun ce stable against acce	onger than 90 calend d stabilization shall b lerated erosion until	ar days after the last land disturbing e maintained in a manner to render the permanent ground stabilization is achiev	
roui ract ctivi urfa RO I tabi echr	icable but in no case lity. Temporary groun ce stable against acce UND STABILIZATION S lize the ground suffici- niques in the table be	onger than 90 calend d stabilization shall b lerated erosion until SPECIFICATION ently so that rain will low:	ar days after the last land disturbing e maintained in a manner to render the permanent ground stabilization is achiev not dislodge the soil. Use one of the	
roui ctivi urfa ROI tabi echr	icable but in no case lity. Temporary groun ce stable against acce UND STABILIZATION S lize the ground suffici- niques in the table be Temporary Stab	onger than 90 calend d stabilization shall b lerated erosion until SPECIFICATION ently so that rain will low: ilization	ar days after the last land disturbing e maintained in a manner to render the permanent ground stabilization is achiev not dislodge the soil. Use one of the <u>Permanent Stabilization</u>	
• Te of • Te of • H • R • M • A • P	icable but in no case lity. Temporary groun ce stable against access UND STABILIZATION Stable below lize the ground suffici- niques in the table below Temporary grass seed cover ther mulches and tackifier offed erosion control pro- ithout temporary grass s ppropriately applied strat lastic sheeting	onger than 90 calend d stabilization shall b elerated erosion until SPECIFICATION ently so that rain will low: ilization ered with straw or ers ducts with or eed w or other mulch	lar days after the last land disturbing e maintained in a manner to render the permanent ground stabilization is achiev not dislodge the soil. Use one of the <u>Permanent Stabilization</u> Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed	
 roui ract ctivi urfa RO tabi echr Te of H Ro of H Ro of A Pl 	icable but in no case lity. Temporary groun ce stable against acce UND STABILIZATION S lize the ground suffici- niques in the table be <u>Temporary Stab</u> emporary grass seed cover ther mulches and tackifie ydroseeding olled erosion control pro- ithout temporary grass s ppropriately applied strat astic sheeting	onger than 90 calend d stabilization shall b elerated erosion until SPECIFICATION ently so that rain will low: ilization ered with straw or ers ducts with or eed w or other mulch	lar days after the last land disturbing e maintained in a manner to render the permanent ground stabilization is achiev not dislodge the soil. Use one of the <u>Permanent Stabilization</u> Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed	

EQUIPMENT AND VEHICLE MAINTENANCE

- 1. Maintain vehicles and equipment to prevent discharge of fluids.
- 2. Provide drip pans under any stored equipment.
- 3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- Collect all spent fluids, store in separate containers and properly dispose as 4. hazardous waste (recycle when possible).
- 5. Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- 6. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- 1. Never bury or burn waste. Place litter and debris in approved waste containers. 2. Provide a sufficient number and size of waste containers (e.g dumpster, trash
- receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- 5. Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- 6. Anchor all lightweight items in waste containers during times of high winds.
- 7. Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility. 8.
- On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE

- 1. Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- 2. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- 3. Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- 5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from
- construction sites.

PORTABLE TOILETS

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- 2. Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- 3. Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- 1. Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- 2. Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- 3. Provide stable stone access point when feasible.
- 4. Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.





4596

STABILIZATION AND MATERIALS HANDLING

PART III

SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections

ere delayed sh	hall be noted in th	e Inspection Record.	Item to Document	Documentation Requirements
Inspect	Frequency (during normal business hours)	Inspection records must include:	 (a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations 	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each
maintained in good working order	Dairy	If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those un- attended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as	shown on the approved E&SC plan.	E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(2) E&SC Measures	At least once per 7 calendar days and within 24	 approved by the Division. 1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 	(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(3) Stormwater	At least once per	 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken. 1. Identification of the discharge outfalls inspected, 	(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
discharge outfalls (SDCs)	7 calendar days and within 24 hours of a rain event \geq 1.0 inch in	 Date and time of the inspection, Name of the person performing the inspection, Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 	(d) The maintenance and repair requirements for all E&SC measures have been performed.	Complete, date and sign an inspection report.
(4) Perimeter of site	At least once per 7 calendar days and within 24	 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken. If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits. 	 (e) Corrective actions have been taken to E&SC measures. 	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.
	event <u>></u> 1.0 inch in 24 hours	 Description, evidence, and date of corrective actions taken, and An explanation as to the actions taken to control future releases. 	2. Additional Documentation to be Kept on In addition to the E&SC plan documents a site and available for inspectors at all time	Site bove, the following items shall be kept on the es during normal business hours, unless the
(5) Streams or wetlands onsite or offsite (where	At least once per 7 calendar days and within 24 hours of a rain	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and	Division provides a site-specific exemption this requirement not practical:	n based on unique site conditions that make
accessible)	event ≥ 1.0 inch in 24 hours	2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.	(a) This General Permit as well as the Ce	rtificate of Coverage, after it is received.
(6) Ground stabilization measures	After each phase of grading	 The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). Documentation that the required ground stabilization measures have been provided within the required 	(b) Records of inspections made during to record the required observations on the Division or a similar inspection form to electronically-available records in lies shown to provide equal access and ut	he previous twelve months. The permittee shall the Inspection Record Form provided by the that includes all the required elements. Use of u of the required paper copies will be allowed if tility as the hard-copy records.
NOTE: The rai	n inspection reset	soon as possible.	3. Documentation to be Retained for Three All data used to complete the e-NOI and a of three years after project completion an	Years Il inspection records shall be maintained for a p d made available upon request [40 CER 122 41]

PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- (a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items,
- (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit, (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include
- properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,
- (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- (f)

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

eriod of the years after project completion and made available upon request. [40 CFK 122.41]

(d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above, Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

SECTION C: REPORTING

1. Occurrences that Must be Reported Permittees shall report the following occurrences:

- (b) Oil spills if:
 - They are 25 gallons or more,
- - (Ref: 40 CFR 302.4) or G.S. 143-215.85.

 - environment.

2. Reporting Timeframes and Other Requirements

858-0368.

Occurrence	R	epoi
(a) Visible sediment	•	Wi
deposition in a	•	Wi
stream or wetland		sec
		Div
		cas
	•	lf t
		rel
		mo
		de
		wit
(b) Oil spills and	٠	Wi
release of		sha
hazardous		loc
substances per Item		
1(b)-(c) above		
(c) Anticipated	•	Ar
bypasses [40 CFR		Th
122.41(m)(3)]		eff
(d) Unanticipated	•	Wi
bypasses [40 CFR	•	Wi
122.41(m)(3)]		qu
(e) Noncompliance	•	Wi
with the conditions	•	Wi
of this permit that		no
may endanger		inc
health or the		be
environment[40		COI
CFK 122.41(I)(7)]		pre
	•	Div
		cas

ORDER OF PRECENDENCE GENERAL

- NOTES/TECHNICAL SPECIFICATIONS THE NOTES CONTAINED HEREIN ARE INTENDED TO SUPPLEMENT THE TECHNICAL SPECIFICATIONS AND PROVIDE EASY REFERENCE FOR THE CONTRACTOR. IN NO CASE SHALL THESE NOTES VOID ANY PART, SECTION OR REQUIREMENT OUTLINED IN THE TECHNICAL SPECIFICATIONS CONTAINED IN THE CONTRACT DOCUMENTS. IF CONFLICTS OCCUR BETWEEN THE TECHNICAL SPECIFICATIONS AND THE NOTES CONTAINED HEREIN, THE TECHNICAL SPECIFICATIONS SHALL SUPERSEDE.
- CONTRACTOR IS CHARGED WITH PERFORMING SITE INVESTIGATIONS TO ASCERTAIN EXISTING SITE CONDITIONS. PHOTOGRAPHIC DOCUMENTATION OF PRE-EXISTING CONSTRUCTION CONDITIONS WILL BE CONDUCTED BY THE ENGINEER FOR DETERMINATION OF COMPLIANCE WITH CONDITIONS NOTED HEREON.
- SENERAL NOTES
- ACCESS TO SITES SHALL BE BY PUBLIC RIGHT-OF-WAYS AND UTILITY EASEMENTS. OTHER ACCESS LOCATIONS REQUIRED SHALL BE SECURED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER. SUPPLEMENTAL EROSION CONTROL MEASURES SHALL BE REQUIRED TO INCLUDE CONSTRUCTION ENTRANCES, SILT FENCING, RESTORATION, ETC. ADDITIONAL MEASURES SHALL BE INCLUDED AS PART OF A SUPPLEMENTAL EROSION CONTROL PLAN PREPARED BY THE CONTRACTOR.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE THE CONSTRUCTION STAGING AREA AT HIS EXPENSE.
- THE CONTRACTOR IS EXPECTED AND REQUIRED TO COOPERATE WITH THE PROPERTY OWNERS AFFECTED BY THE WORK. MAIL ADJOINING PROPERTY OWNER LETTERS TO EFFECTED PROPERTY OWNERS NOTIFYING THEM THAT WORK WILL BE OCCURRING WITHIN THE AREAS ADJOINING THEIR PROPERTIES. THIS LETTER SHALL GIVE PROPERTY OWNERS A MINIMUM OF 14 DAYS WRITTEN NOTICE PRIOR TO COMMENCEMENT OF CONSTRUCTION FOR REMOVAL OF ANY PERSONAL ITEMS FROM THE RIGHT- OF-WAY. THE LETTER OUTLINES THE EXTENT OF THE WORK TO BE PERFORMED TO INCLUDE DRIVEWAY DISRUPTIONS
- CONTRACTOR SHALL MAINTAIN A NEAT AND CLEAN JOB-SITE TO INCLUDE STAGING/STORAGE AREAS AS FOLLOWS - PERFORM DUST CONTROL BY WATERING DAILY OR AS DIRECTED BY
 - THE ENGINEER AND/OR CURRITUCK COUNTY SWEEP STREETS A MINIMUM OF ONCE WEEKLY (FRIDAY) OR AS DIRECTED BY THE ENGINEER AND/OR CURRITUCK COUNTY. BLADE, LEVEL AND RE-COMPACT ALL EXPOSED TRENCHES WEEKLY
 - PERFORM DAILY CLEAN-UP OF ALL DIRT, DEBRIS AND SCRAP MATERIALS. REMOVE EXCESS EQUIPMENT, MATERIALS, TOOLS, ETC. NOT NEEDED.
 - -ANY DRIVEWAY REMOVALS MUST HAVE A TEMPORARY SURFACE INSTALLED WITHIN THE SAME DAY AS REMOVAL. APPROVED SURFACES MAY CONSIST OF EITHER ABC OR MILLINGS.

THE WORK WITHIN RIGHT OF WAY AREAS MUST BE KEPT IN AN ORDERLY AND NEAT FASHION. NO MATERIAL (SOILS, GRAVEL OR OTHER PROJECT FILL) CAN 10. ALL CONSTRUCTION OF SANITARY SEWER MAINS AND APPURTENANCES IN THE BE PLACED DIRECTLY ON ANY STREET SURFACE WITHOUT MATTING BEING PUT DOWN FIRST. ANY DAMAGE TO ANY ROAD SURFACE FROM CONSTRUCTION ACTIVITIES MUST BE REPAIRED AT OWNERS EXPENSE

- EXCESS SUITABLE SOIL EXCAVATED DURING CONSTRUCTION SHALL BE STOCKPILED FOR USE ON THE PROJECT OR DISPOSED OF OFF-SITE AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL NOT BE ALLOWED TO STOCKPILE MATERIALS OR EXCESS MATERIALS IN THE STREET RIGHT-OF-WAYS AT ANY TIME. THE CONTRACTOR SHALL PROVIDE A SUFFICIENT AND SUITABLE STOCKPILE AREA AND LOCATION AT THE CONTRACTOR'S EXPENSE.
- CONTRACTOR SHALL PROVIDE MEASURES DURING CONSTRUCTION TO SECURE THE SITE AND EXCAVATION FROM THE GENERAL PUBLIC AND COMPLY WITH ALL OSHA REGULATIONS. JOB SITE SAFETY IS THE EXCLUSIVE AND SOLE RESPONSIBILITY OF THE CONTRACTOR. OPEN EXCAVATION LEFT UNATTENDED OR OVER NIGHT IS NOT ACCEPTABLE AND SHALL BE FILLED IMMEDIATELY.
- CONTRACTOR SHALL REPAIR OR REPLACE DRIVES DISTURBED BY CONSTRUCTION TO EXISTING OR BETTER CONDITIONS. NO SEPARATE PAYMENT UNLESS OTHERWISE INDICATED.
- CONTRACTOR SHALL PROVIDE TEMPORARY FENCING WHERE FENCES ARE REMOVED FOR CONSTRUCTION. CONTRACTOR SHALL COORDINATE FENCE REMOVAL OR REINSTALLATION WITH INDIVIDUAL PROPERTY OWNERS PRIOR TO REMOVAL. CONTRACTOR SHALL REINSTALL ALL SHEDS, FENCES, ETC. TO AS GOOD OR BETTER THAN EXISTING CONDITIONS UNLESS OTHERWISE INDICATED. (NO SEPARATE PAYMENT).
- CONTRACTOR SHALL REPLACE ALL DISTURBED MAILBOXES, SIGNS, ETC. DISTURBED DURING CONSTRUCTION WITHIN 24 HOURS OF DISTURBANCE. PERMANENT ROAD SIGNAGE DISTURBED SHALL BE REPLACED IMMEDIATELY AND IF NECESSARY ROADWAY SIGNS SHALL BE TEMPORARILY INSTALLED IN A LOCATION CONSISTENT WITH THE NCMUTCD TO PROVIDE CONTINUOUS TRAFFIC AWARENESS OF ROADWAY CONDITIONS. (NO SEPARATE PAYMENT).
- CONTRACTOR SHALL PROVIDE SECURITY FENCING, SECURITY GUARD, AND ANY AND ALL OTHER MEASURES CONTRACTOR DEEMS NECESSARY TO PROTECT EQUIPMENT AND MATERIALS STORED ON THE PROJECT. (NO SEPARATE PAYMENT)
- WHERE CONTRACTOR CEASES WORK OPERATIONS FOR A 72 HOUR PERIOD OR LONGER, SUCH AS HOLIDAYS, ETC., THE FOLLOWING SHALL BE ACCOMPLISHED PRIOR TO THE WORK STOPPAGE.
 - A. CONTRACTOR SHALL STORE ALL EQUIPMENT IN THE CONTRACTOR STAGING AREA OR OFF SITE.
 - B. THE CONTRACTOR SHALL SWEEP ALL STREETS, PERFORM GENERAL CLEANUP AND SHALL PERFORM MAINTENANCE ON ALL EXPOSED PATCHES.
- CONTRACTOR SHALL SCHEDULE WORK AND MATERIAL DELIVERIES SO THAT STORED MATERIAL QUANTITIES ON THE JOB SITE SHALL BE MINIMIZED
- CONTRACTOR SHALL STORE ALL MATERIALS IN THE CONTRACTOR STAGING AREA 72 HOURS PRIOR TO INCORPORATING INTO THE WORK TO REDUCE OBSTRUCTIONS TO TRAFFIC AND INCONVENIENCE TO RESIDENTS. WHERE 17. WHEREVER FOUNDATION MATERIAL IS UNSUITABLE, IT SHALL BE EXCAVATED UNTIL UTILITIES ARE BEING CONSTRUCTED IN EASEMENTS OUT OF TRAFFIC AREAS CONTRACTOR MAY STORE MATERIALS AHEAD OF CONSTRUCTION FOR A DISTANCE NOT GREATER THAN 1800 FEET UNLESS APPROVED OTHERWISE BY THE ENGINEER.
- CLEARING AND GRUBBING SHALL BE RESTRICTED TO PERMANENT EASEMENTS ONLY. CONTRACTOR SHALL LIMIT TREE/BUSH CLEARING IN LINES TO ONLY ABSOLUTELY NECESSARY FOR CONSTRUCTION.

RELATION OF WATER MAINS TO SEWERS

- () LATERAL SEPARATION OF SEWERS AND WATER MAINS. WATER MAINS SHALL BE LAID AT LEAST 10 FEET LATERALLY FROM EXISTING OR PROPOSED SEWERS, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT A 10-FOOT LATERAL SEPARATION -- IN WHICH CASE
- (1) THE WATER MAIN IS LAID IN A SEPARATE TRENCH, WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER: OR
- (2) THE WATER MAIN IS LAID IN THE SAME TRENCH AS THE SEWER WITH THE WATER MAIN LOCATED AT ONE SIDE ON A BENCH OF UNDISTURBED EARTH, AND WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER.
- B) CROSSING A WATER MAIN OVER A SEWER. WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS OVER A SEWER, THE WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT AN 18 INCH VERTICAL SEPARATION--IN WHICH CASE BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF FERROUS MATERIALS AND WITH JOINTS THAT ARE EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF
- THE POINT OF CROSSING.) CROSSING A WATER MAIN UNDER A SEWER. WHENEVER IT IS NECESSAR) FOR A WATER MAIN TO CROSS UNDER A SEWER, BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF FERROUS MATERIALS AND WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING. A SECTION OF WATER MAIN PIPE SHALL BE CENTERED AT THE POINT OF CROSSING.

- CONSTRUCTION SEQUENCE NOTES
- PRIOR TO COMMENCEMENT OF ANY WORK WITHIN EASEMENTS OR RIGHTS-OF-WAYS THE CONTRACTOR IS REQUIRED TO NOTIFY CONCERNED UTILITY COMPANIES IN ACCORDANCE WITH GS 87-102. CONTRACTOR SHALL VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION. NO SEPARATE PAYMENT. EXISTING UTILITIES SHOWN ARE TAKEN FROM MAPS FURNISHED BY VARIOUS UTILITY COMPANIES AND HAVE NOT BEEN PHYSICALLY LOCATED (I.E. TELEPHONE, GAS, CABLE, ETC.).
- 2. THE CONTRACTOR SHALL DIG UP EACH UTILITY WHICH MAY CONFLICT WITH CONSTRUCTION 14 DAYS IN ADVANCE TO VERIFY LOCATIONS (HORIZONTALLY AND VERTICALLY) TO ALLOW THE ENGINEER AN OPPORTUNITY TO ADJUST THE DESIGN TO AVOID CONFLICTS (NO SEPARATE PAYMENT).
- 3. ALL SANITARY SEWER & WATER CONSTRUCTION SHALL BE IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS OF THE NCDENR-DWQ & NCDENR-PWS. STORM DRAINAGE, STREET CONSTRUCTION AND PAVING SHALL BE IN ACCORDANCE WITH THE N.C.D.O.T
- 4. UTILITY SERVICES TO INDIVIDUAL PROPERTIES ARE NOT SHOWN IN THE PROFILES FOR SIMPLICITY OF THE DRAWINGS. SERVICES MAY INCLUDE WATER LATERALS, TELEPHONE, ELECTRIC, CABLE, GAS, ETC.
- 5. CONTRACTOR SHALL COORDINATE WITH UTILITY OWNER AND BE RESPONSIBLE FOR TEMPORARY RELOCATION AND/OR SECURING EXISTING UTILITY POLES AND SIGNS AND/OR UTILITIES IN ACCORDANCE WITH UTILITY OWNER REQUIREMENTS DURING THE UTILITY MAIN INSTALLATION AND STREET CONSTRUCTION. (NO SEPARATE PAYMENT).
- CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORTS FOR UTILITY CROSSINGS AND REPAIR DAMAGES DUE TO CONSTRUCTION TO THE SATISFACTION OF THE UTILITY INVOLVED AT NO ADDITIONAL EXPENSE TO THE OWNER. UNDERGROUND ELECTRICAL CROSSINGS SHALL BE CROSSED IN ACCORDANCE WITH THE NEC AND 23. CONTRACTOR SHALL FURNISH WEIRS, STAND PIPES, PIPE PLUGS, WATER, TECHNICAL SPECIFICATION SECTION UNDERGROUND ELECTRICAL CROSSING
- WHERE DEEMED NECESSARY BY THE ENGINEER THAT A SUBSURFACE DRAINAGE SYSTEM IS REQUIRED, THE CONTRACTOR SHALL PROVIDE ALL MATERIALS, TOOLS, LABOR, EQUIPMENT, TIE-IN'S TO EXISTING DRAINAGE STRUCTURES AND ALL OTHER INCIDENTALS NECESSARY TO PROVIDE COMPLETE INSTALLATION. IMPROPERLY INSTALLED AND NON-FUNCTIONING DRAINAGE SHALL BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE. EXISTING FRENCH DRAINAGE DAMAGED DURING CONSTRUCTION SHALL BE REPLACED AND OR REPAIRED AT NO ADDITIONAL EXPENSE TO THE OWNER.
- (OR AS DIRECTED BY THE ENGINEER) TO PRODUCE A SMOOTH "RIDE". 8. STORM DRAINAGE REPAIRS BY CONTRACTOR DUE TO CONSTRUCTION DAMAGE AND JOINTS EXPOSED DURING CONSTRUCTION SHALL BE INSPECTED BY THE OWNER PRIOR TO BACKFILLING.
 - . CONTRACTOR SHALL PROVIDE ALL LABOR, EQUIPMENT AND MATERIAL AND PERFORM ALL WORK REQUIRED FOR INSTALLATION OF SEWER LINES, MANHOLES AND APPURTENANCES AS OUTLINED ON DRAWINGS AND ON SPECIFICATIONS, ALL OF WHICH BECOME PART OF THE CONTRACT DOCUMENTS.
 - COLLECTION SYSTEMS SHALL BE IN STRICT ACCORDANCE WITH PLANS AND SPECIFICATIONS PREPARED AS PART OF THE CONTRACT DOCUMENTS AND AS APPROVED BY THE BPG, INC. ENGINEER. ALL MATERIALS SHALL BE NEW AND UNUSED. PRIOR TO CONSTRUCTION OF THE APPROVED SANITARY SEWER, CONTRACTOR SHALL PROVIDE FIELD STAKEOUT INCLUDING ADEQUATE LINE AND GRADE STAKES IN ORDER THAT SANITARY SEWER AND APPURTENANCES MAY BE CONSTRUCTED IN ACCORDANCE WITH CONTRACT DRAWINGS.
 - 11. A PRECONSTRUCTION CONFERENCE SHALL BE HELD AT THE COMPLETION OF THE FIELD STAKEOUT WITH THE ENGINEEER AN HIS/HER REPRESENTATIVE CURRITUCK COUNTY REPRESENTATIVE, NCDENR REPRESENTATIVE, AND ANY REQUISITE UTILITY REPRESENTATIVES THAT WILL REQUIRE COORDINATION WITH DURING THE COURSE OF CONSTRUCTION. A MINIMUM OF 2 DAYS NOTICE SHALL BE GIVEN FOR MEETING REPRESENTATIVES.
 - 12. PREPARE PHOTOGRAPHIC DOCUMENTATION OF PRE-EXISTING CONDITIONS OF THE $_{-2}$ PROJECTED CONSTRUCTION ROUTE PRIOR TO COMMENCING WORK.
 - 13. IF ANY DEVIATION IS CONTEMPLATED IN LOCATION OR LINE GRADE OF ANY SEWER. STRUCTURE OR APPURTENANCE AS SHOWN ON THE CONTRACT DRAWINGS, A REVISION OF THE DRAWINGS SHOWING THE PROPOSED DEVIATION SHALL BE SUBMITTED TO THE BPG INC. ENGINEER FOR REVIEW AND APPROVAL BEFORE ANY CHANGES ARE CONSTRUCTED. MINOR FIELD CHANGES MAY BE MADE WITH APPROVAL OF BPG, INC. APPOINTED FIELD INSPECTOR. SHOULD CONTRACTOR DISCOVER AND/OR DAMAGE ANY UNDERGROUND UTILITY FACILITIES, WHICH ARE NOT SHOWN ON DRAWINGS AND/OR MARKED ON THE GROUND, CONTRACTOR SHALL PROMPTLY NOTIFY UTILITY OWNER AND OWNER'S PROJECT REPRESENTATIVE. RELOCATION OF ANY UTILITIES SHALL BE APPROVED AND COORDINATED WITH THE APPROPRIATE UTILITY OWNER.
 - 14. EXCAVATION SHALL CONFORM TO THE LINES AND GRADES SHOWN ON THE PLANS. THE WIDTH OF EXCAVATION FOR TRENCHES SHALL BE A MINIMUM OF 24". EXCAVATION SHALL NOT BE CARRIED BELOW THE ESTABLISHED GRADES AND ANY EXCAVATION BELOW THE REQUIRED LEVEL SHALL BE BACKFILLED WITH SUITABLE, THOROUGHLY COMPACTED GRANULAR BEDDING MATERIAL. CONTRACTOR SHALL INSTALL ALL SHEETING, BRACING, AND SHORING NECESSARY TO PERFORM THE WORK, TO PROTECT EXISTING STRUCTURES AND ALL EXCAVATIONS AS REQUIRED UNDER NORTH CAROLINA OSHA REGULATIONS. COMPLIANCE WITH PROVISIONS OF THE OVERHEAD HIGH VOLTAGE LINE SAFETY ACT IS REQUIRED.
 - 15. DEWATERING EQUIPMENT SHALL BE SIZED TO MAINTAIN THE TRENCH IN A SATISFACTORY DEWATERED CONDITION SUITABLE FOR PIPE LAYING AND BACKFILLING. PIPE LAYING WILL BE PERMITTED ONLY WHERE THE DEPTH OF WATER ⁵ IS MAINTAINED BELOW THE BEDDING MATERIAL. BEDDING MATERIAL SHALL NOT BE PLACED ON UNSTABLE TRENCH MATERIAL.
 - 16. NOT MORE THAN ONE HUNDRED FIFTY FEET (150') OF TRENCH SHALL BE OPENED IN ADVANCE OF THE COMPLETED PIPE LAYING. TRENCH WALLS SHALL BE PROTECTED IN ACCORDANCE WITH CURRENT OSHA REGULATIONS. EXCAVATION AT MANHOLES AND SIMILAR STRUCTURES SHALL PROVIDE A MINIMUM CLEARANCE OF EIGHTEEN INCHES (18") BETWEEN THE OUTER SURFACE OF THE STRUCTURE AND THE EMBANKMENT OR SHEETING
 - A STABLE FOUNDATION IS ACHIEVED. GRANULAR MATERIAL, #67 STONE PER ASTM C 12, SHALL THEN BE PLACED IN SIX INCH (6") LAYERS AND COMPACTED UNTIL THE TRENCH BOTTOM HAS BEEN STABILIZED. STANDARD GRANULAR PIPE BEDDING MATERIAL SHALL BE PLACED IN ACCORDANCE WITH ASTM D 2321 FOR PVC PIPE AND ASTM C 12 FOR DIP.
- THE TEMPORARY EASEMENTS, BETWEEN HOUSES AND ALONG PROPERTY 18. ALL GRAVITY SEWER MAINS, SERVICE LATERALS AND FORCE MAINS SHALL HAVE A MINIMUM COVER OF THREE FEET (3') AS MEASURED FROM TOP OF PIPE TO FINISH GRADE. THE BPG, INC. ENGINEER MAY REQUIRE ADDITIONAL COVER AS NEEDED FOR PIPE PROTECTION. SEWERS, WHICH HAVE A DEPTH OF COVER LESS THAN THREE FEET (3'), SHALL BE APPROVED AND INSTALLED AS PER BPG, INC. ENGINEER'S WRITTEN INSTRUCTIONS.

WATER CROSSING SEWER DETAIL NOT TO SCALE

19. PIPE SHALL BE LAID TRUE TO LINE AND GRADE WITH BELLS UPSTREAM AND SHALL BE JOINTED TOGETHER SUCH THAT THE COMPLETED PIPE WILL HAVE A SMOOTH INVERT. PIPE SHALL BE PUSHED HOME BY HAND. THE USE OF EQUIPMENT (I.E. BACKHOE) SHALL NOT BE PERMITTED. CUTTING OF PIPE SHALL BE PERFORMED BY SAWING, STANDARD BEDDING SHALL BE SHAPED TO THE CURVATURE OF BOTH THE BELL AND BARREL OF THE PIPE. THE TRENCH SHALL BE KEPT FREE OF WATER WHILE THE WORK IS IN PROGRESS. THE ENDS OF THE PIPE SHALL BE CLEANED SO THAT PROPER JOINTS CAN BE MADE. AS THE WORK PROGRESSES. THE INTERIOR OF THE PIPE SHALL BE CLEARED OF DIRT, CEMENT, OR OTHER DELETERIOUS MATERIAL.

20. EXCEPT AS REQUIRED FOR USE OF A LASER LEVEL, EXPOSED END OF ALL PIPE AND FITTINGS SHALL BE FULLY CLOSED TO PREVENT EARTH. WATER OR OTHER SUBSTANCES FROM ENTERING PIPE. TRENCH SHALL BE COMPLETELY BACKFILLED AT END OF EACH WORKDAY. WHEN NEW PIPE IS TIED INTO AN EXISTING MANHOLE, NEW PIPE SHALL BE PLUGGED WITH A STANDARD SEWER PLUG AND SHALL REMAIN PLUGGED UNTIL ALL NEW LINE(S) THAT WILL FLOW TO EXISTING MANHOLE HAVE BEEN COMPLETED, TESTED, AND ACCEPTED.

BACKFILL SHALL BEGIN AT THE TOP OF THE STANDARD GRANULAR BEDDING AND SHALL BE PLACED IN SIX INCH (6") LAYERS FOR THE INITIAL ONE FOOT OVER THE PIPE AND SHALL BE THOROUGHLY TAMPED TO NINETY-FIVE PERCENT (95%) OF THE MAXIMUM THEORETICAL COMPACTION DENSITY AS DETERMINED BY A STANDARD PROCTOR ON THE MATERIAL. REMAINDER OF THE BACKFILL SHALL BE IN TWO FOOT (2') LAYERS PROPERLY TAMPED.

22. COMPLETION: BEFORE CONNECTING TO AN ACTIVE SYSTEM, THE LEAKAGE TESTS SHALL PROMPTLY FOLLOW INSTALLATION OF WASTEWATER PIPE INCLUDING SERVICES AND KEPT WITHIN A MAXIMUM OF 1000 FEET BEHIND THE WASTEWATER PIPE LAYING OPERATION.

PRESSURE GAUGES, STOP WATCHES, AIR COMPRESSOR, VACUUM PUMP, HOSE AND SUCH MATERIALS AND ASSISTANCE AS REQUIRED TO PERFORM THESE TESTS. ALL ACCEPTANCE TESTS SHALL BE CONDUCTED BY CONTRACTOR IN THE PRESENCE OF A BPG, INC. APPOINTED INSPECTOR.

ACCEPTANCE TESTS SHALL NOT BE MADE UNTIL SANITARY SEWER, MANHOLES AND PROPOSED SEWER SERVICE CONNECTIONS, AS SHOWN ON THE APPROVED SEWER PLANS HAVE BEEN INSTALLED THE SEWER TRENCHES (INCLUDING MANHOLES AND CLEANOUT STACKS) BACKFILLED AND COMPACTED TO FINISHED SUB-GRADE.

25. CONTRACTOR SHALL BE RESPONSIBLE AT ALL TIMES FOR MAINTAINING SEWER FLOWS DURING PROJECT TO INCLUDE ANY REQUIRED BY-PASS PUMPING OF WASTEWATER BETWEEN MANHOLES DURING INSTALLATION OF SEWER LINES AND/OR MANHOLES. BY-PASS PUMPING SYSTEM SHALL PROVIDE CONTINUOUS FULL CONVEYANCE AND CONTAINMENT OF WASTEWATER PRESENT DURING THE WORK AND SHALL NOT SURCHARGE THE UPSTREAM PUMP STATION BY MORE THAN TWO (2) FEET ABOVE THE NORMAL EFFLUENT LEVELS.

26. ONCE ACCEPTANCE AND START OF THE COLLECTION SYSTEM HAS BEEN RECIEVED, THE CONTRACTOR SHALL PROCEED WITH THE ABANDONMENT PROCEDURES OF THE EXISTING WASTEWATER COLLECTION SYSTEM AS DESCRIBED HEREON.

- THE WORK IS SUSPENDED
- OWNER
- DEWATERING WASTES.
- EWER SERVICE LATERAL NOTES APPROVAL
- HAMMER TAPS ALLOWED.
- OTHERWISE INDICATED AS DUCTILE IRON
- AND MECHANICAL JOINT FITTINGS
- SHALL BE ONE PIECE MOLDED OR FABRICATED
- 10. SLOPE AND DEPTH OF THE SERVICE LATERAL SHALL BE DETERMINED BY
- INDICATED ON THE DRAWINGS
- PIPE IS 75', 100' FOR 6" PIPE
- WITH SEWER MAIN.
- FLUSHING SANITARY SEWER MAINS.
- ENGINEER OR HIS REPRESENTATIVE
- UNLESS OTHERWISE APPROVED BY ENGINEER.

MANUFACTURED BY HARCO, GPK OR APPROVED EQUAL

THE NOTES CONTAINED HEREIN ARE INTENDED TO SUPPLEMENT THE TECHNICAL SPECIFICATIONS AND PROVIDE EASY REFERENCE FOR THE CONTRACTOR. IN NO CASE SHALL THESE NOTES VOID ANY PART, SECTION OR REQUIREMENT OUTLINED IN THE TECHNICAL SPECIFICATIONS CONTAINED IN THE CONTRACT DOCUMENTS.

TRENCH DEWATERING DURING SEWER LINE INSTALLATION ALL GROUND WATER WHICH MAY BE FOUND IN THE TRENCHES AND ANY WATER WHICH MAY GET INTO THEM FROM ANY CAUSE WHATSOEVER SHALL BE PUMPED OR BAILED OUT SO THAT THE TRENCH SHALL BE DRY DURING THE PIPE LAYING PERIOD. NO WATER SHALL BE PERMITTED TO REACH CONCRETE UNTIL IT HAS SET SUFFICIENTLY, ALL WATER PUMPED FROM THE TRENCHES SHALL BE DISPOSED OF IN A MANNER SATISFACTORY TO THE OWNER. CONTRACTOR SHALL PROVIDE AT LEAST TWO (2) PUMPS FOR EACH TRENCH OPENED IN WET GROUND AND AT THE SAME TIME, HE SHALL HAVE ONE (1) PUMP IN RESERVE.

. IF, DURING ANY TIME THAT CONTRACTOR IS PERMITTED TO LAY PIPE IN A TRENCH CONTAINING UNAVOIDABLE TRENCH WATER AND CONSTRUCTION IS INTERRUPTED FOR ANY REASON, THE OPEN ENDS OF PIPE SHALL BE CLOSED BY WATERTIGHT PLUGS OR CAPS. OR OTHER MEANS APPROVED BY THE OWNER. IN ANY CASE, SUCH PROTECTION SHALL BE PROVIDED WHEN WORK IS SUSPENDED OVERNIGHT OR ON WEEKENDS AND HOUDAYS REGARDLESS OF THE CONDITION OF THE TRENCH WITH RESPECT TO WATER AT THE TIME THAT

3. CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL STRUCTURES, INCLUDING PIPES AND MANHOLES, AGAINST ANY TENDENCY TO FLOAT UNDER CONDITIONS OF HIGH WATER, WHETHER DUE TO HIGH GROUND WATER OR FLOOD CONDITIONS ON THE PROJECT SITE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO TAKE WHATEVER STEPS MAY BE REQUIRED. INCLUDING THE INSTALLATION AND OPERATION OF PUMPS AND PUMPING SYSTEMS, WELL POINTS OR RELIEF DEVICES, TO PREVENT ANY STRUCTURE FROM FLOATING DURING CONSTRUCTION.

4. COST OF THE NECESSARY PUMPS, WELL POINTS OR OTHER APPURTENANCES REQUIRED TO PREVENT FLOTATION SHALL BE INCLUDED IN THE UNIT PRICES BID IN THE PROPOSAL FOR THE VARIOUS BID ITEMS, AND NO EXTRA COMPENSATION SHALL BE ALLOWED FOR SUCH WORK. ANY DAMAGE WHICH MAY OCCUR TO ANY PART OF THE WORK AS THE RESULT OF THE FLOTATION EFFECT OF GROUND OR FLOOD WATERS SHALL BE REPAIRED IN A MANNER FULLY SATISFACTORY TO THE OWNER, AT NO ADDITIONAL COST TO THE

CONTRACTOR SHALL PROVIDE AND PLACE ALL NECESSARY FLUMES OR OTHER CHANNELS OF ADEQUATE SIZE TO CARRY TEMPORARILY ALL STREAMS, BROOKS, STORMWATER OR OTHER WATER, WHICH MAY FLOW ALONG OR ACROSS THE LINES OF THE PIPE LINE. ALL FLUMES OR CHANNELS THUS UTILIZED SHALL BE TIGHT SO AS TO PREVENT LEAKAGE INTO THE TRENCHES. WATER PUMPED FROM TRENCHES SHALL BE LED TO NATURAL WATERCOURSES. EXISTING SEWERS SHALL NOT BE EMPLOYED AS A DRAIN FOR THE REMOVAL OF

CONTRACTOR SHALL MAKE UP STACK AND SUBMIT TO ENGINEER FOR APPROVAL AND SHALL SUBMIT TAPPING SADDLE IF USED TO ENGINEER FOR

HOLE IN SANITARY SEWER MAIN MUST BE CUT WITH SHELL CUTTER. NO

LATERAL SHALL CONFORM TO ASTM SPECS. D-3034 SDR-35 UNLESS

ALL PIPE AND FITTINGS SHALL BE 4" OR 6" UNLESS OTHERWISE SPECIFIED ALL D.I. PIPE SHALL HAVE AN INTERIOR LINING OF CERAMIC EPOXY OR FUSED CALCIUM ALUMINATE CEMENT WITH FUSED CALCIUM ALLUMINATE AGGREGATES. THE ENTIRE D.I. LATERAL SHALL BE COMPRISED OF D.I. PIPE

ALL CONNECTIONS SHALL HAVE RUBBER GASKET SEALS INSTALLED. THE CONTRACTOR SHALL USE SDR 35 P.V.C. WYE FOR CONNECTION TO SDR 35 P.V.C. PIPE OR DI TEE FOR CONNECTION TO DUCTILE IRON PIPE. PVC WYE INSTALLATION OTHER THAN AS SHOWN MUST BE ENGINEER APPROVED

9. TAPPING PROCESS SHOWN SHALL BE USED FOR ALL SANITARY SEWER

THE TOPOGRAPHY OF THE LOT AS APPROVED BY THE ENGINEER OR AS 11. SLOPE OF LATERALS SHALL CONFORM TO 1/4" PER FOOT MIN. FOR 4" PIPE

AND 1/8" PER FOOT MIN. FOR 6" PIPE. MAXIMUM CLEAN OUT SPACING FOR 4" 12. ENTIRE SEWER LATERAL ASSEMBLY SHALL BE AIR TESTED CONCURRENTLY

13. INDIVIDUAL LATERALS SHALL BE CLEANED AND FLUSHED PRIOR TO

14. LATERAL SHALL NOT BE BACK-FILLED UNTIL INSPECTED BY THE PROJECT

15. WYE CONNECTIONS SHALL NOT BE USED TO TIE LATERALS INTO A MANHOLE 16. IF BENDS ARE APPROVED BY THE PROJECT ENGINEER, STONE BEDDING IS REQUIRED TO BE INSTALLED FROM UNDISTURBED SOIL TO BOTTOM OF BEND. 17. PVC COMBINATION SHALL BE 2 PIECE TEE-WYE, GASKETED, SDR35, AS

ITILITY GENERAL NOTES

- PRIOR TO COMMENCEMENT OF ANY WORK WITHIN EASEMENTS OR RIGHTS-OF-WAYS THE CONTRACTOR IS REQUIRED TO NOTIFY CONCERNED UTILITY COMPANIES IN ACCORDANCE WITH GS 87-102. CONTRACTOR SHALL VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION. NO SEPARATE PAYMENT. EXISTING UTILITIES SHOWN ARE TAKEN FROM MAPS FURNISHED BY VARIOUS UTILITY COMPANIES AND HAVE NOT BEEN PHYSICALLY LOCATED (i.e. TELEPHONE, GAS, CABLE, ETC.).
- 2. THE CONTRACTOR SHALL DIG UP EACH UTILITY WHICH MAY CONFLICT WITH CONSTRUCTION 14 DAYS IN ADVANCE TO VERIFY LOCATIONS (HORIZONTALLY AND VERTICALLY) TO ALLOW THE ENGINEER AN OPPORTUNITY TO ADJUST THE DESIGN TO AVOID CONFLICTS (NO SEPARATE PAYMENT).
- 3. ALL SANITARY SEWER & WATER CONSTRUCTION SHALL BE IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS OF THE NCDENR-DWQ & NCDENR-PWS. STORM DRAINAGE, STREET CONSTRUCTION AND PAVING SHALL BE IN ACCORDANCE WITH THE N.C.D.O.T.
- 4. UTILITY SERVICES TO INDIVIDUAL PROPERTIES ARE NOT SHOWN IN THE PROFILES FOR SIMPLICITY OF THE DRAWINGS. SERVICES MAY INCLUDE WATER LATERALS, TELEPHONE, ELECTRIC, CABLE, GAS, ETC.
- 5. CONTRACTOR SHALL COORDINATE WITH UTILITY OWNER AND BE RESPONSIBLE FOR TEMPORARY RELOCATION AND/OR SECURING EXISTING UTILITY POLES AND SIGNS AND/OR UTILITIES IN ACCORDANCE WITH UTILITY OWNER REQUIREMENTS DURING THE UTILITY MAIN INSTALLATION AND STREET CONSTRUCTION. (NO SEPARATE PAYMENT).
- CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORTS FOR UTILITY CROSSINGS AND REPAIR DAMAGES DUE TO CONSTRUCTION TO THE SATISFACTION OF THE UTILITY INVOLVED AT NO ADDITIONAL EXPENSE TO THE OWNER. UNDERGROUND ELECTRICAL CROSSINGS SHALL BE CROSSED IN ACCORDANCE WITH THE NEC AND TECHNICAL SPECIFICATION SECTION UNDERGROUND ELECTRICAL CROSSING
- 7. WHERE DEEMED NECESSARY BY THE ENGINEER THAT A SUBSURFACE DRAINAGE SYSTEM IS REQUIRED. THE CONTRACTOR SHALL PROVIDE ALL MATERIALS, TOOLS, LABOR, EQUIPMENT, TIE-IN'S TO EXISTING DRAINAGE STRUCTURES AND ALL OTHER INCIDENTALS NECESSARY TO PROVIDE COMPLETE INSTALLATION IN ACCORDANCE WITH CITY OF FAYETTEVILLE STANDARDS. IMPROPERLY INSTALLED AND NON-FUNCTIONING DRAINAGE SHALL BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE. EXISTING FRENCH DRAINAGE DAMAGED DURING CONSTRUCTION SHALL BE REPLACED AND OR REPAIRED AT NO ADDITIONAL EXPENSE TO THE OWNER.
- ANY DRIVEWAY CULVERTS DAMAGED DURING CONSTRUCTION SHALL BE EITHER REPAIRED OR REPLACED AT CONTRACTOR'S EXPENSE. FILTER FABRIC CLOTH SHALL BE PLACED OVER EITHER CULVERT ENDS DURING THE COURSE OF CONSTRUCTION. ALL EX. DRAINAGE INFRASTRUCTURE WILL BE RETURNED TO PRE-EXISTING CONDITIONS PRIOR TO FINAL PROJECT APPROVALS.

GENERAL NOTES SANITARY SEWER UTILITY CLEANOUT ELEVATIONS AND/OR LOCATIONS MAY BE ADJUSTED IN THE FIELD AS DIRECTED BY THE ENGINEER WHEN NECESSARY. CLEANOUT STACK TOP ELEVATION IS DETERMINED BY INTERPOLATING FIELD DATA AND MAY NOT BE EXACT. CLEANOUT ELEVATION TOP SHALL BE SET IN ACCORDANCE WITH THE

TYPICAL DETAIL DESCRIBED HEREON. (NO SEPARATE PAYMENT).

- WHERE SANITARY SEWER MAINS ARE TO BE CONSTRUCTED WITHIN 20' OF EXISTING RESIDENCES SPECIAL CONSIDERATION SHALL BE GIVEN TO MINIMIZE UNDERMINING OR OTHERWISE DISTURBING EXISTING RESIDENCES ADJACENT TO THE SEWER MAIN. THE CONTRACTOR SHALL USE A RUBBER TIRED BACK HOE AND NO MECHANICAL COMPACTION FOUIPMENT IN THESE AREAS THE TRENCH SHALL BE SHORED ADEQUATELY TO PREVENT ANY SLOTHING OF THE SIDE SLOPES. SUITABLE BACK FILL SHALL BE PLACED IN THE TRENCH. CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR REPAIR OF STRUCTURES, FOUNDATIONS, FOOTINGS, ETC. DAMAGED DUE TO CONSTRUCTION.
- 3. SANITARY SEWER MANHOLE DEFLECTION ANGLE'S ARE 180 DEGREES UNLESS NOTED OTHERWISE. ALL INVERT ELEVATIONS ARE SHOWN TO THE MANHOLE CENTERLINE

CLEANOUT COVER ASSEMBL

