

**GENERAL NOTES:**

1. PROJECT NAME: THE FOST TRACT - PLANNED DEVELOPMENT - RESIDENTIAL - CONSTRUCTION PHASE 3  
[APPROVED PRELIMINARY PLAT PHASES 6A & 7A]
2. APPLICANT/DEVELOPER: MOYOCK DEVELOPMENT, LLC  
227 CARATOKE HIGHWAY  
MOYOCK, NC 27958
3. PROPERTY DATA:  
ADDRESS: CARATOKE HIGHWAY, MOYOCK, NC 27958  
PIN: 0015-000-0086-0000  
RECORD DOCUMENT(S): DB:1524, PG:456; PC:S, SL:176  
PROPERTY ZONING: PD-R (PLANNED DEVELOPMENT - RESIDENTIAL)
4. F.I.R.M. DATA:  
ZONE X PER F.I.R.M. MAP NOS. 3721803100 K, 3721803200 K, & 3721804000 K. ALL HAVING AN EFFECTIVE DATE DECEMBER 21, 2018. USE OF LAND WITHIN A FLOODWAY OR FLOOD PLAIN IS SUBSTANTIALLY RESTRICTED BY CHAPTER 7 OF THE CURRITUCK COUNTY UNIFIED DEVELOPMENT ORDINANCE.
5. THIS PROPERTY CONTAINS ACRE "404" JURISDICTIONAL WETLANDS AS SHOWN AND CONFIRMED BY USACE ACTION ID # SAW 2018-00838, DATED APRIL 30, 2018, AND MAY REQUIRE U.S. CORP OF ENGINEERS APPROVAL PRIOR TO DEVELOPMENT OF THE PROPERTY.
6. SECTION 7.6.5 OF THE CURRITUCK U.D.O. SUBSTANTIALLY RESTRICTS DEVELOPMENT WITHIN A 30' RIPARIAN BUFFER TO CERTAIN WETLANDS.
7. EXISTING CONDITION INFORMATION BASED ON A COMBINATION OF THE FOLLOWING:  
• 2012 AERIAL IMAGERY OBTAINED FROM NCONEMAP.COM  
• FIELD TOPOGRAPHIC SURVEY DATA BY BISSELL PROFESSIONAL GROUP.  
• ELEVATIONS ARE REFERENCED TO NAVD 1988 VERTICAL DATUM.
8. ALL UTILITIES ARE TO BE UNDERGROUND.
9. A 10' EASEMENT FOR UTILITIES AND DRAINAGE ALONG REAR AND SIDE PROPERTY LINES AND A 15' EASEMENT FOR UTILITIES AND DRAINAGE ALONG FRONT PROPERTY LINE SHALL BE ESTABLISHED. PEDESTRIAN ACCESS AND A 25' DRAINAGE EASEMENT SHALL BE ESTABLISHED ALONG ALL DRAINAGEWAYS SERVING MORE THAN 5 ACRES. A BLANKET DRAINAGE, UTILITY, AND PEDESTRIAN ACCESS EASEMENT SHALL BE ESTABLISHED ACROSS ALL OPEN SPACE AREAS. A 50' DRAINAGE EASEMENT SHALL BE ESTABLISHED ALONG ROWLAND CREEK CANAL.
10. ALL DOUBLE FRONTOGE LOTS SHALL INCLUDE A 5' NON-ACCESS EASEMENT ALONG THE MOST TRAVELED STREET. THESE EASEMENTS WILL BE PROVIDED ON THE FINAL PLATS PREPARED FOR RECORDING OF THE SUBDIVISION.

**DEVELOPMENT NOTES:**

1. TOTAL PROPERTY AREA: 225.35 AC.  
FUTURE DEVELOPMENT AREA (NOT A PART): 89.37 AC.  
PHASES 1 - 6 & 7A RESIDENTIAL PROJECT AREA: 135.98 AC.

2. PHASES 6A & 7A RESIDENTIAL DEVELOPMENT SUMMARY  
PROPOSED LOT AREA: 2.06 AC.  
PROPOSED R/W AREA: 1.35 AC.  
PROPOSED OPEN SPACE AREA: 1.91 AC.  
TOTAL AREA: 5.31 AC.  
# OF PROPOSED SINGLE FAMILY LOTS: 0  
# OF PROPOSED TOWNSCAPE LOTS: 39  
PROPOSED SANDRA RD R/W WIDTH: 50 FT.  
PROPOSED SANDRA RD ROADWAY WIDTH: 25-33 FT. (W/ C&G)  
PROPOSED SANDRA RD LENGTH: 563 L.F.±  
PROPOSED ALLEY R/W WIDTH: 30 FT.  
PROPOSED ALLEY ROADWAY WIDTH: 20 FT.  
PROPOSED ALLEY ROADWAY LENGTH: 1,082 L.F.±

3. PHASES 6A & 7A RESIDENTIAL DEVELOPMENT IMPERVIOUS COVERAGE DATA (BUA):  
MAXIMUM TOTAL LOT COVERAGE: 89,611 SF  
ASPHALT ROADWAY: 17,783 SF  
CONCRETE ALLEY: 31,588 SF  
SIDEWALKS: 8,673 SF  
ALLOWANCE FOR MISC. AMENITIES: 2,500 SF  
TOTAL COVERAGE: 150,155 SF (3.45 AC.)

4. DISTURBED AREA SUMMARY:  
EXISTING CONSTRUCTION PHASES 1 & 2 DISTURBED AREA: 172 ACRES  
THIS PHASE 3 IS LOCATED WITHIN THE EXISTING DISTURBED AREA ABOVE

# CONSTRUCTION DRAWINGS FOR THE FOST TRACT PLANNED DEVELOPMENT - RESIDENTIAL CONSTRUCTION PHASE 3

APPROVED PRELIMINARY PLAT PHASES 6A & 7A

MOYOCK TOWNSHIP

CURRITUCK COUNTY

NORTH CAROLINA

Sheet  
Number

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

Sheet Title

COVER SHEET, DEVELOPMENT NOTES & SITE LOCATION

EXISTING FEATURES & CONDITIONS PLAN

DEVELOPMENT OVERVIEW PLAN

GRADING, DRAINAGE & STORMWATER MANAGEMENT PLAN

EROSION & SEDIMENT CONTROL PLAN & SEQUENCE

WASTEWATER COLLECTION & WATER MAIN EXTENSION PLAN

LANDSCAPING, BUFFERING, SIGNAGE & LIGHTING PLAN

SANDRA ROAD PLAN & PROFILE (0+00-5+24)

LEIF STREET PLAN & PROFILE (0+00-4+04)

HEATH STREET PLAN & PROFILE (0+00-3+67)

ROWAN STREET PLAN & PROFILE (0+00-4+80)

ROADWAY, DRAINAGE & MISC. CONSTRUCTION DETAILS

ROADWAY, SIDEWALK & MISC. CONSTRUCTION DETAILS

EROSION AND SEDIMENT CONTROL NOTES & DETAILS

NCG01-GROUND STABILIZATION & MATERIALS HANDLING

NCG01-SELF INSPECTION, RECORDKEEPING & REPORTING

WASTEWATER COLLECTION TYP. CONSTRUCTION DETAILS

WASTEWATER COLLECTION TYP. CONSTRUCTION DETAILS

**FINAL DRAWING  
NOT RELEASED FOR  
CONSTRUCTION**

**STORMWATER CERTIFICATE**


I, [REDACTED] OWNER/AGENT HEREBY CERTIFY THE INFORMATION INCLUDED ON THIS AND ATTACHED PAGES IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE.

ON THE PLAN TITLED, THE FOST TRACT PD-R PHASE 6A & 7A CONSTRUCTION DRAWINGS, THE FOLLOWING PLANS, GRADES, DRAINS, AND STORMWATER MANAGEMENT PLAN, STORMWATER DRAINAGE IMPROVEMENTS SHALL BE INSTALLED ACCORDING TO THESE PLANS AND SPECIFICATIONS AND APPROVED BY CURRITUCK COUNTY. YEARLY INSPECTIONS ARE REQUIRED AS PART OF THE STORMWATER PLAN. THE OWNER IS RESPONSIBLE FOR ALL MAINTENANCE REQUIRED. CURRITUCK COUNTY ASSUMES NO RESPONSIBILITY FOR THE DESIGN, MAINTENANCE, OR PERFORMANCE OF THE STORMWATER IMPROVEMENTS.

DATE	OWNER/AGENT
------	-------------

THE FOLLOWING PERMITS ARE REQUIRED PRIOR TO PROJECT CONSTRUCTION:


PERMIT	AGENCY	REFERENCE NUMBER	DATE OF ISSUANCE
SEDIMENTATION AND EROSION CONTROL PERMIT	N.C.D.E.Q. - DIVISION OF LAND RESOURCES	CURRI-2020-010/CURRI-2022-017	2/26/2020-4/6/2022
STORMWATER MANAGEMENT PERMIT	N.C.D.E.Q. - DIVISION OF LAND RESOURCES	SW7200202	
WATERLINE EXTENSION AUTHORIZATION TO CONSTRUCT	N.C.D.E.Q. - PUBLIC WATER SUPPLY		
WASTEWATER COLLECTION SYSTEM PERMIT	N.C.D.E.Q. - DIVISION OF WATER RESOURCES		
CURRITUCK COUNTY PRELIMINARY PLAT & USE PERMIT	CURRITUCK COUNTY BOARD OF COMMISSIONERS	PB18-23	3/15/2021
CURRITUCK COUNTY CONSTRUCTION AUTHORIZATION	CURRITUCK COUNTY PLANNING STAFF	-	




North Carolina  
One-Call Center Inc.



Know what's below  
Call before you dig.






**FINAL DRAWING**  
NOT RELEASED FOR  
CONSTRUCTION


Bissell Professional Group  
Firm License # C-956  
3512 North Croatan Highway  
P.O. Box 1068  
Kitty Hawk, North Carolina 27949  
(252) 261-3266  
FAX (252) 261-1760

# EARLING FEATURES & CONDITIONS PLAN




BY	DATE	DESCRIPTION
NO. 042639	04/24/24	SCALE: 1" = 200'
APPROVED: BPG	CHECKED: MSB	
FILE: 465100PH6-7	PROJECT NO: 4651	


2 OF 18





**FINAL DRAWING**  
NOT RELEASED FOR  
CONSTRUCTION


<b>FINAL DRAWING</b> <b>NOT RELEASED FOR</b> <b>CONSTRUCTION</b>		<table border="1"> <tr> <td>NO.</td> <td>DATE</td> </tr> <tr> <td colspan="2">  </td> </tr> <tr> <td>DATE:</td> <td>SCALE: 1" = 30'</td> </tr> <tr> <td>DESIGNED: BPG</td> <td>CHECKED: MSB</td> </tr> <tr> <td>DRAWN: KFW/DMK</td> <td>APPROVED: BPG</td> </tr> <tr> <td colspan="2">SHEET: 4 OF 18</td> </tr> <tr> <td colspan="2">CAD FILE: 465100PH6-7</td> </tr> <tr> <td colspan="2">PROJECT NO: 4651</td> </tr> </table>		NO.	DATE			DATE:	SCALE: 1" = 30'	DESIGNED: BPG	CHECKED: MSB	DRAWN: KFW/DMK	APPROVED: BPG	SHEET: 4 OF 18		CAD FILE: 465100PH6-7		PROJECT NO: 4651	
		NO.	DATE																
																			
DATE:	SCALE: 1" = 30'																		
DESIGNED: BPG	CHECKED: MSB																		
DRAWN: KFW/DMK	APPROVED: BPG																		
SHEET: 4 OF 18																			
CAD FILE: 465100PH6-7																			
PROJECT NO: 4651																			
240																			













ALIGNMENT: LEIF STREET (STA 0+00 - 4+04)

SCALE: HOR.: 1"=30' (PLAN VIEW)



**FINAL DRAWING**  
NOT RELEASED FOR  
CONSTRUCTION





ALIGNMENT: LEIF STREET (STA 0+00 - 4+04)

SCALE: HOR.: 1"=30' VERT.: 1"=3' (PROFILE VIEW)

CONSTRUCTION DRAWINGS - PHASE 3  
THE FOST TRACT PD-R - PHASES 6A & 7A  
CURRITUCK COUNTY  
NORTH CAROLINA  
PROJECT NO. 465100PH6-7  
DRAWN BY: M. KLEIN  
APPROVED BY: BPG  
checked by: 769422DF05646D4C8  
DATE: 10/24/24  
DESIGNED BY: BPG  
APPROVED BY: BPG  
SHEET: 9 OF 18  
CAD FILE: 465100PH6-7  
PROJECT NO: 4651

**BISSELL PROFESSIONAL GROUP**  
3572 North Carolina Highway  
Box 202  
Carolina 27949  
FAX (252) 261-1760  
Engineers, Planners, Surveyors  
and Environmental Specialists



THIS DOCUMENT IS THE SOLE PROPERTY OF CURRITUCK COUNTY, NORTH CAROLINA. IT IS THE PROPERTY OF THE COUNTY AND IS LOANED TO THE CONTRACTOR IN THE PERFORMANCE OF THE CONTRACT. NO COPIES OF THIS DOCUMENT ARE TO BE MADE WITHOUT THE EXPRESS WRITTEN CONSENT OF CURRITUCK COUNTY, NORTH CAROLINA. BISSELL, PRINCIPAL OF BPG, INC., COPYRIGHT 2005.



ALIGNMENT: HEATH STREET (STA 0+00 - 3+00)  
SCALE: HOR.: 1"=30' VERT.: 1"=3' (PROFILE VIEW)

SCALE. HOR.. 1-30 VERT.. 1-3 (PROFILE

**FINAL DRAWING**  
NOT RELEASED FOR  
CONSTRUCTION



FINAL DRAWING  
NOT RELEASED FOR  
CONSTRUCTION





ROWAN STREET  
PLAN & PROFILE (0+00 - 4+80)

CONSTRUCTION DRAWINGS - PHASE 3  
THE FOST TRACT PD-R - PHASES 6A & 7A  
CURRICK COUNTY  
MOYOCK TOWNSHIP  
NORTH CAROLINA


**BISSELL**  
Bissell Professional Group  
Civil Engineering  
3572 North Carolina Highway  
P.O. Box 1068  
Cary, NC 27513  
(919) 465-2256  
(252) 261-1760  
PROFESSIONAL GROUP  
Engineers, Planners, Surveyors  
and Environmental Specialists

THIS DOCUMENT IS THE SOLE PROPERTY OF CURRICK COUNTY, NORTH CAROLINA. IT IS TO BE USED EXCLUSIVELY IN THE PLANNING, DESIGN, CONSTRUCTION, AND OPERATION OF THE PROJECT IDENTIFIED ON THE COVER. ANY FURTHER COPIES OR USE OF THIS DOCUMENT IN WHOLE OR IN PART, OR THE MODIFICATION OF ANY DETAIL OR DESIGN IS NOT TO BE MADE WITHOUT THE EXPRESS WRITTEN CONSENT OF CURRICK COUNTY. BISSELL, PRINCIPAL OF BPG, INC., COPYRIGHT 2005.

11 OF 18  
CAD FILE: 465100PH6-7  
PROJECT NO: 4651




## CURB & GUTTER COLLECTION SECTION



## CURB & GUTTER DUMP SECTION


NOT TO SCALE NCDOT STD 846.01



## SECTION PARKING LOT & SIDEWALK DETAIL

**GENERAL CURB & GUTTER NOTES:**

1. PLACE CONTRACTION JOINTS AT 10' INTERVALS, EXCEPT THAT A 15' SPACING MAY BE USED WHEN A MACHINE IS USED OR WHEN SATISFACTORY SUPPORT FOR THE FACE FORM CAN BE OBTAINED WITHOUT THE USE OF TEMPLATES AT 10' INTERVALS.
2. JOINT SPACING MAY BE ALTERED IF REQUIRED BY ENGINEER.
3. CONTRACTION JOINTS MAY BE INSTALLED WITH THE USE OF TEMPLATES OR FORMED BY OTHER APPROVED METHODS. CONSTRUCT NON-TEMPLATE FORMED JOINTS A MIN. OF 1-1/2" DEEP.
4. FILL ALL CONSTRUCTION JOINTS, EXCEPT IN 8"X6" MEDIAN CURB, WITH JOINT FILLER AND SEALER.
5. SPACE EXPANSION JOINTS AT 90' INTERVALS AND ADJACENT TO ALL RIGID OBJECTS.



SECTION A-A SECTION B-B C

**CURB & GUTTER TRANSITION SECTION**

**FINAL DRAWING**  
NOT RELEASED FOR  
CONSTRUCTION

PROJECT: <b>THE FOST TRACT PD-R - PHASES 6A &amp; 7A</b>		REVISIONS	
		NO.	DATE
CARTOGRAPHIC INFORMATION		ROADWAY, DRAINAGE & MIS.C.	
MOYOCK TOWNSHIP		CONSTRUCTION DETAILS	
CURRITUCK COUNTY		NORTH CAROLINA	
THIS DOCUMENT IS THE SOLE PROPERTY OF BPG, INC. OF KITTY HAWK, NORTH CAROLINA. THE REPRODUCTION IN WHOLE OR PART, OR THE MODIFICATION OF ANY DETAIL OR DESIGN IS NOT TO BE MADE WITHOUT THE EXPRESS WRITTEN CONSENT OF MARK S. BISSELL, PRINCIPAL OF BPG, INC., COPYRIGHT 2005.			
CONSTRUCTION DRAWINGS - PHASE 3			



GENERAL PROJECT NOTES:	
1. PROJECT NAME: THE FOST TRACT PD-R MOYOCK, CURRITUCK COUNTY, NORTH CAROLINA	
2. DEVELOPER: MOYOCK CURRITUCK, LLC 417 CARATOKO HWY, UNIT D MOYOCK, NC 27929	
3. PROJECT DESCRIPTION: PLANNED DEVELOPMENT RESIDENTIAL SUBDIVISION 4. NEAREST RECEIVING STREAM: ROWLAND CREEK CANAL - INDEX NUMBER: 30-1-2-2-5-1-2-1 5. STREAM CLASSIFICATION: C-5w; RIVER BASIN: PASQUOTANK	
6. PROJECT AREA TABULATION:	
TOTAL PROPERTY AREA: 225.35 AC.	
EXISTING DISTURBED AREA: 172.00 AC. CURRI-2020-010	
PROPOSED ADDITIONAL DISTURBED AREA: 0.00 AC.	
TOTAL DISTURBED AREA: 172.00 AC.	
AREA CALCULATION NOTE: All areas have been calculated utilizing properties within the Autocad software.	
MATERIAL BALANCE NOTE: All excavated material occurring during the course of construction shall remain on-site for roadway construction and lot grading. See SCHEDULE OF LAND DISTURBING ACTIVITIES provided on Sheet 5 of this set for an estimated cut fill material balance for the project.	
WETLAND NOTE: The property contains 404 jurisdictional wetlands as noted on the cover sheet.	
STABILIZATION NOTE: The angle of graded slopes and fills shall be no greater than the angle that can be retained by vegetative cover or other adequate erosion control devices or measures. In addition, all slopes and fills shall be stabilized <b>WITHIN 14 CALENDAR DAYS OF COMPLETION</b> of any phase of grading, be planted or otherwise provided with temporary or permanent ground cover, devices, or structures sufficient to retain erosion. Additionally, certain critical areas as identified on the plan, such as but not limited to, perimeter dikes, swales, sites steeper than 3:1, and areas located within High Quality Waters Zones, must be temporarily or permanently stabilized <b>WITHIN 7 CALENDAR DAYS OF COMPLETION</b> of any phase of grading in these areas. A permanent ground cover for all disturbed areas must be provided <b>WITHIN 15 WORKING DAYS OR 90 CALENDAR DAYS</b> (whichever is shorter) following completion of construction or development.	

## SEDIMENTATION AND EROSION CONTROL NOTES:


## A. NARRATIVE AND SITE DATA:

FOST IS A PLANNED RESIDENTIAL SUBDIVISION (PD-R) BEING DEVELOPED ALONG THE SOUTH SIDE OF NC HWY 163, JUST WEST OF GUINEA RD. (SR 1214) IN MOYOCK TOWNSHIP, CURRITUCK COUNTY. THE COMMUNITY INCLUDES A MIXTURE OF RESIDENTIAL, SINGLE FAMILY HOMES, COMMERCIAL BUILDINGS, AND MULTIFAMILY BUILDINGS. THESE DIVISIONS DETAIL THE SITE AS A PLANNED COMMUNITY THAT WILL INCLUDE (8) ADDITIONAL TOWNS HOME BUILDINGS CONTAINING (39) UNITS. IN ADDITION TO THE BUILDINGS, CONSTRUCTION ACTIVITIES WILL INCLUDE ASSOCIATIVE ROADWAY, UTILITY, DRAINAGE, LIGHTING, LANDSCAPING AND AMENITY IMPROVEMENTS.

PHASE 3 CONSTRUCTION ACTIVITIES ARE LOCATED **WITHIN THE 172 ACRE DISTURBANCE LIMITS ESTABLISHED FOR CONSTRUCTION OF THE PRIOR 2 PHASES. NO ADDITIONAL LAND DISTURBANCE AREA IS BEING PROPOSED WITH PHASE 3.**

EXISTING TOPOGRAPHY ACROSS THIS PHASE OF THE PROJECT SITE IS GENERALLY FLAT, WITH SLOPES BETWEEN 0-1% AND ELEVATIONS RANGING FROM 5-10 FT MSL. SURROUNDING AREAS ARE DEVELOPED WITH EXISTING ROADWAYS, TOWN HOMES AND SINGLE FAMILY LOTS CONSTRUCTED IN PRIOR PHASES OF THE SUBDIVISION. STORMWATER RUNOFF FROM PHASE 3 WILL BE DIRECTED TO A SERIES OF EXISTING WET-DETENTION PONDS LOCATED WITHIN THE COMMUNITY.


PURSUANT TO THE USA SOIL SURVEY MANUAL OF CURRITUCK COUNTY, SITE SOILS ARE COMPOSED OF A MIXTURE OF ROANOKE FINE SANDY LOAM, CAPE FEAR LOAM AND WASA MUCH. ROANOKE SERIES SOILS ARE DESCRIBED AS BEING NEARLY LEVEL AND POORLY DRAINED, WITH PERMEABILITY RATES RANGING FROM 0.6 INHR AT THE SURFACE, UP TO 20 INHR AT DEPTHS OF 12 FEET. WASA SERIES SOILS ARE ALSO DESCRIBED AS NEARLY LEVEL AND VERY POORLY DRAINED SOILS WITH PERMEABILITY RATES SIMILAR TO THOSE OF THE ROANOKE SERIES. WASA SERIES SOILS ARE DESCRIBED AS NEARLY LEVEL, VERY POORLY DRAINED SOIL ON BROAD FLATS WITH PERMEABILITY RATES RANGING FROM 0.6 INHR AT THE SURFACE TO 20 INHR AT DEPTHS OF 50 IN AND GREATER.



TO PROVIDE TEMPORARY SOIL STABILIZATION BY PLANTING GRASSES AND LEGUMES TO AREAS THAT WOULD REMAIN BARE FOR MORE THAN 14 CALENDAR DAYS, OR 7 DAYS IN IDENTIFIED CRITICAL AREAS, WHERE PERMANENT COVER IS NOT NECESSARY OR APPROPRIATE.

## LAND DISTURBANCE &amp; STABILIZATION DETAIL

NOT TO SCALE



## ROLLED EROSION CONTROL MATTING (R.E.C.M.) SPECIFICATIONS:

- All areas identified on these plans as requiring an erosion control matting shall be lined with a protective covering to minimize erosion and protect seed until permanent vegetation is established.
- Covering shall be composed of a biodegradable material to minimize impact.
- Mulching with straw or other organic materials can be utilized only when it will not impede the establishment of permanent vegetation. Mulches must be properly anchored which may be difficult in some environments. An example is straw mulch with jute netting stapled or pinned in place.
4. Recommended for this application, R.E.C.M. shall be installed according to manufacturer specifications for channel linings. An example is a woven straw or wooden fiber Excelsior matting.

## CONSTRUCTION SEQUENCE SCHEDULE

## CONSTRUCTION ACTIVITY

Construction Access- Construction entrance, construction routes, equipment parking areas

Sediment Traps & Barriers  
Basic traps, sediment fences, & outlet protection

Runoff Control-  
Diversions, perimeter dikes, water bars, and outlet protection

Runoff Conveyance System-  
Stabilized stream banks, storm drains, ditches, inlet & outlet protection, slope drains

Land Clearing & Grading-  
Site preparation- cutting, filling & grading, sediment traps, barriers, diversions, drains, surface roughening

Surface Stabilization-  
Temporary & permanent seeding, mulching, sodding, rip rap.

Building Construction-  
Buildings, utilities, paving.

Landscaping & Final Stabilization-  
Topsoiling, trees & shrubs, permanent seeding, mulching, sodding, rip rap

## SCHEDULE CONSIDERATION

First hand-disturbing activity-Stabilize bare areas immediately with gravel & temporary vegetation as construction takes place.

Install principal basins after construction site is accessed. Install additional traps and barriers as needed during grading.

Install key practices after principal sediment traps and before land grading.

5. Ensure that fill material is free of brush, rubbish, rocks, logs, stumps, building debris, and other materials inappropriate for constructing stable fills.

6. Place fill in layers not to exceed 9 inches in thickness, and compact the layers as required to reduce erosion, slippage, settlement, or other related problems.

7. Do not incorporate frozen material or soft, mucky, or highly compressible materials into fill slopes.

8. Do not place fill in a frozen foundation, due to possible subsidence and slippage.

9. Keep diversions and other water conveyance measures free of sediment during all phases of development.

10. Handle seeps or springs encountered during construction in accordance with approved methods.

11. Following completion of any phase of grading, provide a groundcover (temporary or permanent) on all exposed slopes within 14 calendar days, or 7 calendar days in areas identified on the plan; and, a permanent groundcover for all disturbed areas within 15 working days or 90 calendar days (whichever is shorter) following completion of construction or development.

12. Provide adequate protection from erosion for all topsoil stockpiles, borrow areas, and spoil areas.

MAINTENANCE

Precisely check all graded areas & the supporting erosion & sedimentation control practices, especially after heavy rainsfalls. Promptly remove all sediment from diversions and other water-disposal practices. If washouts or breaks occur, repair them immediately. Prompt maintenance of small-eroded areas before they become significant gullies is an essential part of an effective erosion & sedimentation control plan.

Mulch-

Do not mulch Bermuda Grass. For Tall Fescue seed, apply 4,000-lb/acre straw.

Anchor straw by tacking with asphalt, netting, or a mulch-anchoring tool. A disk with blades set nearly straight can be used as a mulch-anchoring tool.

Maintenance-

1. It is highly recommended that soils be tested and amended as found necessary. Soil tests are not tested follow these recommendations:

Apply 3,000-lb/acre of ground agricultural limestone and 500 lb/acre of

10-10-10 starter fertilizer, or 50 lb/acre nitrogen from turf-type

slow-release fertilizer. Add 25-50 lb/acre nitrogen at 2-3 week intervals through midsummer.

Seeding Recommendations for Early Fall through Early Spring

SEEDING DATES - August to March (early fall and spring recommended)

Species Rate

Kentucky 31 Tall Fescue 6 lb/1,000 sf (broadcast seed)

SEEDING NOTES-

1. Sprig or sod- Moisture is essential during initial establishment. Sod must be

kept watered for 2-3 weeks, but can be planted earlier or later than sprigs.

2. Soil Amendments-

Follow recommendations of soil tests or apply 2,000 lb/acre ground

agricultural limestone and 750 lb/acre 10-10-10 fertilizer.

3. Mulch-

Apply 4,000-lb/acre straw. Anchor straw by tacking with asphalt, netting, or

a mulch-anchoring tool. A disk with blades set nearly straight can be used as a mulch-anchoring tool.

Maintenance-

Reseed if growth is not fully adequate. Reseed, fertilize and mulch

immediately following erosion or other damage.

Seeding Recommendations for Fall

SEEDING DATES- August 15 to December 30

SEEDING MIXTURE

Species Rate

Winter Rye (grain) 120 (Annual Ryegrass shall not be used)

Annual Lespideza 50

(Kobe)

\*Note: Annual Lespideza when duration of temporary cover is not to extend

beyond June

Soil Amendments-

Follow recommendations of soil tests or apply 2,000 lb/acre ground

agricultural limestone and 750 lb/acre 10-10-10 fertilizer.

4. Mulch-

Apply 4,000-lb/acre straw. Anchor straw by tacking with asphalt, netting, or

a mulch-anchoring tool. A disk with blades set nearly straight can be used as a mulch-anchoring tool.

Maintenance-

Re-seed and re-fertilize damaged areas immediately. Topdress with 50 lb/acre of

nitrogen in March. If it is necessary to extend temporary cover beyond June

15, overseed with 50 lb/acre Kobe Lespideza in late February or Early March.

5. Sodding Waterways

1. Prepare soil surface as described above.

2. Lay sod strips perpendicular to the direction of flow, with the lateral joints staggered in a brick-like pattern.

3. Do not sod on grave, frozen soils, or soils that have been treated recently with steriliants or herbicides.

4. Lay the first row of sod in a straight line with subsequent rows placed perpendicular to the first, right over left, and over other. Stagger strips in a

brick-like pattern. Be sure that the sod is not stretched or overlapped and that all joints are butted tightly to prevent voids. Use a knife or sharp spade

to trim and fit irregular shaped areas.

5. Install strips of sod with their longest dimension perpendicular to the slope.

On slopes of 1:3 or greater, or wherever erosion may be a problem, secure

down each strip of sod.

6. As sodding of clearly defined areas is completed, roll sod to provide good

contact between roots and soil.

7. After rolling, irrigate until the soil is wet 4 inches below the sod.

8. Keep sodded areas moist to a depth of 4 inches until the grass takes

root. This can be determined by tugging on the sod.

9. Mowing should not be attempted until the sod is firmly rooted, usually

2-3 weeks.

6. Sodding Specifications

Sod Quality

-Sod should be machine cut at a uniform depth of 1/2-2 inches

-Sod should not have been cut in excessively wet or dry weather.

-Sod size should be standard size as determined by the supplier,

uniform, and uniform.

-Sections of sod should be strong enough to support their own weight and

retain their size and shape when lifted by one end.

-Harvest, delivery, and installation of sod should take place within a period

of 36 hours.

7. Soil Amendments-

Apply lime and fertilizer according to soil tests or apply 2,000 lb/acre of

pulverized agricultural limestone and 1,000 lb/acre 10-10-10 fertilizer in the

5-10-10 in spring.

Prior to laying sod, clear the soil surface of trash, debris, roots, branches,

stones, and clods larger than 2 inches in diameter. Fill or level spots in

#### GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

#### SECTION E: GROUND STABILIZATION

##### Required Ground Stabilization Timeframes

Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

**Note:** After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

#### GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
• Temporary grass seed covered with straw or other mulches and tackifiers	• Permanent grass seed covered with straw or other mulches and tackifiers
• Hydroseeding	• Geotextile fabrics such as permanent soil reinforcement matting
• Rolled erosion control products with or without temporary grass seed	• Hydroseeding
• Appropriately applied straw or other mulch	• Shrubs or other permanent plantings covered with mulch
• Plastic sheeting	• Uniform and evenly distributed ground cover sufficient to restrain erosion
	• Structural methods such as concrete, asphalt or retaining walls
	• Rolled erosion control products with grass seed

#### POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the *NC DWR List of Approved PAMS/Flocculants*.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the *NC DWR List of Approved PAMS/Flocculants* and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

#### EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment.
- Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

#### LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers.
- Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility.
- On business days, clean up and dispose of waste in designated waste containers.

#### PAINT AND OTHER LIQUID WASTE


- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

#### PORTABLE TOILETS

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

#### EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



#### CONCRETE WASHOUTS

- Do not discharge concrete or cement slurry from the site.
- Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

#### HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

#### HAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.

FINAL DRAWING  
NOT RELEASED FOR  
CONSTRUCTION



PROJECT	THE FOST TRACT PD-R - PHASES 6A & 7A	NCG01 - GROUND STABILIZATION & MATERIALS HANDLING
NO.	CURRY TOWNSHIP	NORTH CAROLINA
REVISIONS	BY	
NO. DATE DESCRIPTION		

15 OF 18  
CAD FILE: 465100D1-PH6-7  
PROJECT NO: 4651

### PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

#### SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event $\geq 1.0$ inch in 24 hours	1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDCs)	At least once per 7 calendar days and within 24 hours of a rain event $\geq 1.0$ inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event $\geq 1.0$ inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event $\geq 1.0$ inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

### PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items,
- The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,
- Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,
- Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,
- Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

### NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

### PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

#### SECTION B: RECORDKEEPING

##### 1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC measures.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

##### 2. Additional Documentation to be Kept on Site

In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- This General Permit as well as the Certificate of Coverage, after it is received.
- Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

##### 3. Documentation to be Retained for Three Years

All data used to complete the e-NOL and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

### PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

#### SECTION C: REPORTING

##### 1. Occurrences that Must be Reported

Permittees shall report the following occurrences:

- Visible sediment deposition in a stream or wetland.
- Oil spills if:
  - They are 25 gallons or more,
  - They are less than 25 gallons but cannot be cleaned up within 24 hours,
  - They cause sheen on surface waters (regardless of volume), or
  - They are within 100 feet of surface waters (regardless of volume).
- Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- Anticipated bypasses and unanticipated bypasses.
- Noncompliance with the conditions of this permit that may endanger health or the environment.

##### 2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment deposition in a stream or wetland	<ul style="list-style-type: none"> <li><b>Within 24 hours</b>, an oral or electronic notification.</li> <li><b>Within 7 calendar days</b>, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis.</li> <li>If the stream is named on the <a href="#">NC 303(d) list</a> as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions.</li> </ul>
(b) Oil spills and release of hazardous substances per Item 1(b)-(c) above	<ul style="list-style-type: none"> <li><b>Within 24 hours</b>, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.</li> </ul>
(c) Anticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> <li><b>A report at least ten days before the date of the bypass, if possible.</b> The report shall include an evaluation of the anticipated quality and effect of the bypass.</li> </ul>
(d) Unanticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> <li><b>Within 24 hours</b>, an oral or electronic notification.</li> <li><b>Within 7 calendar days</b>, a report that includes an evaluation of the quality and effect of the bypass.</li> </ul>
(e) Noncompliance with the conditions of this permit that may endanger health or the environment [40 CFR 122.41(l)(7)]	<ul style="list-style-type: none"> <li><b>Within 24 hours</b>, an oral or electronic notification.</li> <li><b>Within 7 calendar days</b>, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(l)(6)].</li> <li>Division staff may waive the requirement for a written report on a case-by-case basis.</li> </ul>



NORTH CAROLINA  
Environmental Quality


FINAL DRAWING  
NOT RELEASED FOR  
CONSTRUCTION

16 OF 18  
CAD FILE:  
465100D1-PH6-7  
PROJECT NO:  
4651

**BISSELL PROFESSIONAL GROUP**  
Bissell Professional Group  
352 North Corporate Highway  
Suite 200  
Charlotte, NC 28217  
P.O. Box 2026  
FAX (704) 261-1760  
Engineers, Planners, Surveyors  
and Environmental Specialists

IN THIS DOCUMENT IS THE SOLE PROPERTY OF THE STATE OF NORTH CAROLINA. IT MAY NOT BE COPIED, REPRODUCED, OR ALTERED IN WHOLE OR IN PART, OR THE MODIFICATION OF ANY DETAIL OR DESIGN IS NOT TO BE MADE WITHOUT THE EXPRESS WRITTEN CONSENT OF BISSELL, PRINCIPAL OF BISSELL, INC. COPYRIGHT 2005.

CONSTRUCTION DRAWINGS - PHASE 3



## ORDER OF PRECEDENCE GENERAL NOTES/TECHNICAL SPECIFICATIONS

- THE NOTES CONTAINED HEREIN ARE INTENDED TO SUPPLEMENT THE CONTRACT DOCUMENTS AND ARE NOT A SUBSTITUTE FOR THE CONTRACTOR. IN NO CASE SHALL THESE NOTES VOID ANY PART, SECTION OR REQUIREMENT OUTLINED IN THE TECHNICAL SPECIFICATIONS CONTAINED IN THE CONTRACT DOCUMENTS. IF CONFLICTS OCCUR BETWEEN THE TECHNICAL SPECIFICATIONS AND THE NOTES CONTAINED HEREIN, THE TECHNICAL SPECIFICATIONS SHALL SUPERSEDE.
- CONTRACTOR IS CHARGED WITH PERFORMING SITE INVESTIGATIONS TO ASCERTAIN EXISTING SITE CONDITIONS. PHOTOGRAPHIC DOCUMENTATION OF EXISTING CONSTRUCTION CONDITIONS WILL BE CONDUCTED BY THE ENGINEER FOR DETERMINATION OF COMPLIANCE WITH CONDITIONS NOTED HEREIN.

## GENERAL NOTES

- ACCESS TO SITES SHALL BE BY PUBLIC RIGHT-OF-WAYS AND UTILITY EASEMENTS. OTHER ACCESS LOCATIONS REQUIRED SHALL BE SECURED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER. SUPPLEMENTAL EROSION CONTROL MEASURES SHALL BE REQUIRED TO INCLUDE CONSTRUCTION ENTRANCES, SILT FENCING, RESTORATION, ETC. ADDITIONAL MEASURES SHALL BE INCLUDED AS PART OF A SUPPLEMENTAL EROSION CONTROL PLAN PREPARED BY THE CONTRACTOR.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE THE CONSTRUCTION STAGING AREA AT HIS EXPENSE.
- THE CONTRACTOR IS EXPECTED AND REQUIRED TO COOPERATE WITH THE PROPERTY OWNERS AFFECTED BY THE WORK. MAIL ADJOINING PROPERTY OWNER LETTERS TO EFFECTED PROPERTY OWNERS NOTIFYING THEM THAT WORK WILL BE OCCURRING WITHIN THE AREAS ADJOINING THEIR PROPERTIES. THIS LETTER SHALL GIVE PROPERTY OWNERS A MINIMUM OF 14 DAYS WRITTEN NOTICE PRIOR TO COMMENCEMENT OF CONSTRUCTION FOR REMOVAL OF ANY PERSONAL ITEMS FROM THE RIGHT-OF-WAY. THE LETTER OUTLINES THE EXTENT OF THE WORK TO BE PERFORMED TO INCLUDE DRIVEWAY CLOSURES.
- CONTRACTOR SHALL MAINTAIN A NEAT AND CLEAN JOB-SITE TO INCLUDE STAGING/STORAGE AREAS AS FOLLOWS:
  - PERIODIC DUST CONTROL BY WATERING DAILY OR AS DIRECTED BY THE ENGINEER AND/OR CURRITUCK COUNTY.
  - SWEEP STREETS A MINIMUM OF ONCE WEEKLY (FRIDAY) OR AS DIRECTED BY THE ENGINEER AND/OR CURRITUCK COUNTY.
  - BLADE, LEVEL AND RE-COMPACT ALL EXPOSED TRENCHES WEEKLY (OR AS DIRECTED BY THE ENGINEER) TO PRODUCE A SMOOTH "RIDE".
  - PERIODIC DAILY CLEAN-UP OF ALL DIRT, DEBRIS AND SCRAP MATERIALS.
  - REMOVE EXCESS EQUIPMENT, MATERIALS, TOOLS, ETC. NOT NEEDED.
  - ANY DRIVEWAY REMOVALS MUST HAVE A TEMPORARY SURFACE INSTALLED WITHIN THE SAME DAY AS REMOVAL. APPROVED SURFACES MAY CONSIST OF EITHER ABR. OR MILLINGS.

THE WORK WITHIN RIGHT-OF-WAY AREAS MUST BE KEPT IN AN ORDERLY AND NEAT FASHION. NO MATERIAL (SOILS, GRAVEL OR OTHER PROJECT FILL) CAN BE PLACED DIRECTLY ON ANY STREET SURFACE WITHOUT MATTING BEING PUT DOWN FIRST. ANY DAMAGE TO ANY ROAD SURFACE FROM CONSTRUCTION ACTIVITIES MUST BE REPAIRED AT OWNERS EXPENSE.

- EXCESS SUITABLE SOIL EXCAVATED DURING CONSTRUCTION SHALL BE STOCKPILED FOR USE ON THE PROJECT OR DISPOSED OF OFF-SITE AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL NOT BE ALLOWED TO STOCKPILE MATERIALS OR EXCESS MATERIALS IN THE STREET RIGHT-OF-WAYS AT ANY TIME. THE CONTRACTOR SHALL PROVIDE A SUFICIENT AND SUITABLE STOCKPILE AREA AND LOCATION AT THE CONTRACTOR'S EXPENSE.

- CONTRACTOR SHALL PROVIDE SECURITY MEASURES DURING CONSTRUCTION TO SECURE THE SITE AND EXCAVATION FROM THE GENERAL PUBLIC AND COMPLY WITH ALL OSHA REGULATIONS. JOB SITE SAFETY IS THE EXCLUSIVE AND SOLE RESPONSIBILITY OF THE CONTRACTOR. OPEN EXCAVATION LEFT UNATTENDED OR OVER NIGHT IS NOT ACCEPTABLE AND SHALL BE FILLED IMMEDIATELY.

- CONTRACTOR SHALL REPAIR OR REPLACE DRIVES DISTURBED BY CONSTRUCTION TO EXISTING OR BETTER CONDITIONS. NO SEPARATE PAYMENT UNLESS OTHERWISE INDICATED.

- CONTRACTOR SHALL PROVIDE TEMPORARY FENCING WHERE FENCES ARE REMOVED FOR CONSTRUCTION. CONTRACTOR SHALL COORDINATE FENCE REMOVAL OR REINSTALLATION WITH INDIVIDUAL PROPERTY OWNERS PRIOR TO REMOVAL. CONTRACTOR SHALL REINSTALL ALL SHEDS, FENCES, ETC. TO AS GOOD OR BETTER THAN EXISTING CONDITIONS UNLESS OTHERWISE INDICATED. (NO SEPARATE PAYMENT).

- CONTRACTOR SHALL REPLACE ALL DISTURBED MAILBOXES, SIGNS, ETC. DISTURBED DURING CONSTRUCTION WITHIN 24 HOURS OF DISTURBANCE. PERMANENT ROAD SIGN DISTURB SHALL BE REPLACED IMMEDIATELY AND IF NECESSARY ROADWAY SIGNS SHALL BE TEMPORARILY INSTALLED IN A LOCATION CONSISTENT WITH THE NC MUTCD TO PROVIDE CONTINUOUS TRAFFIC AWARENESS OF ROADWAY CONDITIONS. (NO SEPARATE PAYMENT).

- CONTRACTOR SHALL PROVIDE SECURITY FENCING, SECURITY GUARD, AND ANY AND ALL OTHER MEASURES CONTRACTOR DEEMS NECESSARY TO PROTECT EQUIPMENT AND MATERIALS STORED ON THE PROJECT. (NO SEPARATE PAYMENT).

- WHERE CONTRACTOR CEASES WORK OPERATIONS FOR A 72 HOUR PERIOD OR LONGER SUCH AS HOLIDAYS, ETC. THE FOLLOWING SHALL BE ACCOMPLISHED PRIOR TO THE WORK STOPPAGE.
  - CONTRACTOR SHALL STORE ALL EQUIPMENT IN THE CONTRACTOR STAGING AREA OR OFF SITE.
  - THE CONTRACTOR SHALL SWEEP ALL STREETS, PERFORM GENERAL CLEANUP AND SHALL PERFORM MAINTENANCE ON ALL EXPOSED PATCHES.

- CONTRACTOR SHALL SCHEDULE WORK AND MATERIAL DELIVERIES SO THAT STORED MATERIAL QUANTITIES ON THE JOB SITE SHALL BE MINIMIZED.

- CONTRACTOR SHALL STORE ALL MATERIALS IN THE CONTRACTOR STAGING AREA 72 HOURS PRIOR TO INCORPORATING INTO THE WORK TO REDUCE OBSTRUCTIONS TO TRAFFIC AND INCONVENIENCE TO RESIDENTS. WHERE UTILITIES ARE BEING CONSTRUCTED IN EASEMENTS OUT OF TRAFFIC AREAS CONTRACTOR MAY STORE MATERIALS AHEAD OF CONSTRUCTION FOR A DISTANCE NOT GREATER THAN 1800 FEET UNLESS APPROVED OTHERWISE BY THE ENGINEER.

- CLEARING AND GRUBBING SHALL BE RESTRICTED TO PERMANENT EASEMENTS ONLY. CONTRACTOR SHALL LIMIT TREE/BUSH CLEARING IN THE TEMPORARY EASEMENTS, BETWEEN HOUSES AND ALONG PROPERTY LINES TO ONLY ABSOLUTELY NECESSARY FOR CONSTRUCTION.

## RELATION OF WATER MAINS TO SEWERS

(A) LATERAL SEPARATION OF SEWERS AND WATER MAINS. WATER MAINS SHALL BE LAID AT LEAST 10 FEET LATERALLY FROM EXISTING OR PROPOSED SEWERS. UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT A 10-Foot LATERAL SEPARATION--WHICH CASE:

(1) THE WATER MAIN IS LAID IN A SEPARATE TRENCH, WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER. THE WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT 18 INCH VERTICAL SEPARATION--IN WHICH CASE BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF THE SAME MATERIAL AND WITH JOINTS THAT ARE EQUAL TO THE WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING.

(2) THE WATER MAIN IS LAID IN THE SAME TRENCH AS THE SEWER WITH THE WATER MAIN LOCATED AT ONE SIDE ON A BENCH OF UNDISTURBED EARTH, AND WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER. WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS OVER A SEWER, THE WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT 18 INCH VERTICAL SEPARATION--IN WHICH CASE BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF THE SAME MATERIAL AND WITH JOINTS THAT ARE EQUAL TO THE WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING.

(C) CROSSING A WATER MAIN UNDER A SEWER. WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS UNDER A SEWER, BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF THE SAME MATERIAL AND WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING. A SECTION OF WATER MAIN PIPE SHALL BE CENTERED AT THE POINT OF CROSSING.

## CONSTRUCTION SEQUENCE NOTES

- PRIOR TO COMMENCEMENT OF ANY WORK WITHIN EASEMENTS OR RIGHTS-OF-WAYS THE CONTRACTOR IS REQUIRED TO NOTIFY CONCERNED UTILITY COMPANIES IN ACCORDANCE WITH GS 87-102. CONTRACTOR SHALL VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION. NO SEPARATE PAYMENT. EXISTING UTILITIES SHOWN ARE TAKEN FROM MAPS FURNISHED BY VARIOUS UTILITY COMPANIES AND HAVE NOT BEEN PHYSICALLY LOCATED (I.E. TELEPHONE, GAS, CABLE, ETC.).
- THE CONTRACTOR SHALL DIG UP EACH UTILITY WHICH MAY CONFLICT WITH CONSTRUCTION 14 DAYS IN ADVANCE TO VERIFY LOCATIONS (HORIZONTALLY AND VERTICALLY) TO ALLOW THE ENGINEER AN OPPORTUNITY TO ADJUST THE DESIGN TO AVOID CONFLICTS (NO SEPARATE PAYMENT).
- ALL SANITARY SEWER & WATER CONSTRUCTION SHALL BE IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS OF THE NCDENR-DWQ & NCDENR-PWS. STORM DRAINAGE, STREET CONSTRUCTION AND PAVING SHALL BE IN ACCORDANCE WITH THE N.C.D.O.T.
- UTILITY SERVICES TO INDIVIDUAL PROPERTIES ARE NOT SHOWN IN THE PROFILES FOR SIMPLICITY OF THE DRAWINGS. SERVICES MAY INCLUDE WATER LATERALS, TELEPHONE, ELECTRIC, CABLE, GAS, ETC.
- CONTRACTOR SHALL COORDINATE WITH UTILITY OWNER AND BE RESPONSIBLE FOR TEMPORARY RELOCATION AND/OR SECURING EXISTING UTILITY POLES AND SIGNS AND/OR UTILITIES IN ACCORDANCE WITH UTILITY OWNER REQUIREMENTS DURING THE UTILITY MAIN INSTALLATION AND STREET CONSTRUCTION. (NO SEPARATE PAYMENT).
- BACKFILL SHALL BEGIN AT THE TOP OF THE STANDARD GRANULAR BEDDING AND SHALL BE PLACED IN SIX INCH (6") LAYERS FOR THE INITIAL ONE FOOT OVER THE PIPE AND SHALL BE THOROUGHLY TAMPED TO NINETY-FIVE PERCENT (95%) OF THE MAXIMUM THEORETICAL COMPACTION DENSITY AS DETERMINED BY A STANDARD PROCTOR ON THE MATERIAL. REMAINDER OF THE BACKFILL SHALL BE IN TWO FOOT (2") LAYERS PROPERLY TAMPED.
- COMPLETION: BEFORE CONNECTING TO AN ACTIVE SYSTEM, THE LEAKAGE TESTS SHALL PROMPTLY FOLLOW INSTALLATION OF WASTEWATER PIPE, INCLUDING SERVICES AND KEPT WITHIN A MAXIMUM OF 1000 FEET BEHIND THE WASTEWATER PIPE LAYING OPERATION.
- CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORTS FOR UTILITY CROSSINGS AND REPAIR DAMAGES DUE TO CONSTRUCTION TO THE SATISFACTION OF THE UTILITY INVOLVED AT NO ADDITIONAL EXPENSE TO THE OWNER. UNDERGROUND ELECTRICAL CROSSINGS SHALL BE CROSSED IN ACCORDANCE WITH THE NEC AND TECHNICAL SPECIFICATION SECTION UNDERGROUND ELECTRICAL CROSSING.
- WHERE DEEMED NECESSARY BY THE ENGINEER THAT A SUBSURFACE DRAINAGE SYSTEM IS REQUIRED, THE CONTRACTOR SHALL PROVIDE ALL MATERIALS, TOOLS, LABOR, EQUIPMENT, TIE-UPS TO EXISTING DRAINAGE STRUCTURES AND ALL OTHER INCIDENTALS NECESSARY TO PROVIDE COMPLETE INSTALLATION IN ACCORDANCE WITH CITY OF FAYETTEVILLE STANDARDS. IMPROPERLY INSTALLED AND NON-FUNCTIONING DRAINAGE SHALL BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE. EXISTING FRENCH DRAINAGE DAMAGED DURING CONSTRUCTION SHALL BE REPLACED AND OR REPAIRED AT NO ADDITIONAL EXPENSE TO THE OWNER.
- ANY DRIVEWAY CULVERTS DAMAGED DURING CONSTRUCTION SHALL BE EITHER REPAIRED OR PLACED AT CONTRACTOR'S EXPENSE. FILTER FABRIC CLOTH SHALL BE PLACED OVER EITHER CULVERT ENDS DURING THE COURSE OF CONSTRUCTION. ALL EX. DRAINAGE INFRASTRUCTURE WILL BE RETURNED TO PRE-EXISTING CONDITIONS PRIOR TO FINAL PROJECT APPROVALS.

- ONCE ACCEPTANCE AND START OF THE COLLECTION SYSTEM HAS BEEN RECEIVED, THE CONTRACTOR SHALL PROCEED WITH THE ABANDONMENT PROCEDURES OF THE EXISTING WASTEWATER COLLECTION SYSTEM AS DESCRIBED HEREON.
- THE NOTES CONTAINED HEREIN ARE INTENDED TO SUPPLEMENT THE TECHNICAL SPECIFICATIONS AND PROVIDE EASY REFERENCE FOR THE CONTRACTOR. IN NO CASE SHALL THESE NOTES VOID ANY PART, SECTION OR REQUIREMENT OUTLINED IN THE TECHNICAL SPECIFICATIONS CONTAINED IN THE CONTRACT DOCUMENTS.

## TRENCH Dewatering During Sewer Line Installation

- A PRECONSTRUCTION CONFERENCE SHALL BE HELD AT THE COMPLETION OF THE FIELD STAKEOUT WITH THE ENGINEER AND HIS/HER REPRESENTATIVE, CURRITUCK COUNTY REPRESENTATIVE, NCDENR REPRESENTATIVE, AND ANY REQUISITE UTILITY REPRESENTATIVES THAT WILL REQUIRE COORDINATION DURING THE COURSE OF CONSTRUCTION. A MINIMUM OF 2 DAYS NOTICE SHALL BE GIVEN FOR MEETING REPRESENTATIVES.
- PREPARE PHOTOGRAPHIC DOCUMENTATION OF PRE-EXISTING CONDITIONS OF THE PROJECTED CONSTRUCTION ROUTE PRIOR TO COMMENCING WORK.
- IF ANY DEVIATION IS CONTEMPLATED IN LOCATION OR LINE GRADE OF ANY SEWER, STRUCTURE OR APPURTENANCE AS SHOWN ON THE CONTRACT DRAWINGS, A REVISION OF THE DRAWINGS SHOWING THE PROPOSED DEVIATION SHALL BE MADE BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. IN ANY CASE, SUCH PROTECTION SHALL BE PROVIDED WHEN WORK IS SUSPENDED OVERNIGHT OR ON WEEKENDS AND HOLIDAYS, REGARDLESS OF THE CONDITION OF THE TRENCH WITH RESPECT TO WATER AT THE TIME THAT THE WORK IS SUSPENDED.

- CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL STRUCTURES, INCLUDING PIPES AND MANHOLES, AGAINST ANY TENDENCY TO FLOAT OUT UNDER CONDITIONS OF HIGH WATER, WHETHER DUE TO HIGH GROUND WATER OR FLOOD CONDITIONS ON THE PROJECT SITE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO TAKE WHATEVER STEPS MAY BE REQUIRED, INCLUDING THE INSTALLATION AND OPERATION OF PUMPS AND PUMPING SYSTEMS, WELL POINTS OR RELIEF DEVICES, TO PREVENT ANY STRUCTURE FROM FLOATING DURING CONSTRUCTION.

- COST OF THE NECESSARY PUMPS, WELL POINTS OR OTHER APPURTENANCES REQUIRED TO PREVENT FLOATATION SHALL BE INCLUDED IN THE UNIT PRICES BID IN THE PROPOSAL FOR THE VARIOUS BID ITEMS, AND NO EXTRA COMPENSATION SHALL BE ALLOWED FOR SUCH WORK. ANY DAMAGE WHICH MAY OCCUR TO ANY PART OF THE WORK AS THE RESULT OF THE FLOATATION EFFECT OF GROUND OR FLOOD WATERS SHALL BE REPAIRED IN A MANNER FULLY SATISFACTORY TO THE OWNER, AT NO ADDITIONAL COST TO THE OWNER.

- CONTRACTOR SHALL PROVIDE AND PLACE ALL NECESSARY FLUMES OR OTHER CHANNELS OF ADEQUATE SIZE TO CARRY TEMPORARILY ALL STREAMS, BROOKS, STORMWATER OR OTHER WATER, WHICH MAY FLOW ALONG OR ACROSS THE LINES OF THE PIPE LINE. ALL FLUMES OR CHANNELS THUS UTILIZED SHALL BE TIGHT SO AS TO PREVENT LEAKAGE INTO THE TRENCHES. WATER PUMPED FROM TRENCHES SHALL BE LED TO NATURAL WATERCOURSES. EXISTING SEWERS SHALL NOT BE EMPLOYED AS A DRAIN FOR THE REMOVAL OF DEWATERING WASTES.

- DEWATERING EQUIPMENT SHALL BE SIZED TO MAINTAIN THE TRENCH IN A SAUER-DRY. DEWATERING CONSTRUCTION SUITABLE FOR PIPE LAYING AND BACKFILLING PIPE LAYING WILL BE PERMITTED WHERE THE DEPTH OF WATER IS MAINTAINED BELOW THE BEDDING MATERIAL. BEDDING MATERIAL SHALL NOT BE PLACED ON UNSTABLE TRENCH MATERIAL.

- MORE THAN ONE HUNDRED FIFTY FEET (150') OF TRENCH SHALL BE OPENED IN ADVANCE OF THE COMPLETED PIPE LAYING. TRENCHES SHALL BE PROTECTED IN ACCORDANCE WITH CURRENT OSHA REGULATIONS. EXCAVATION AT MANHOLES AND SIMILAR STRUCTURES SHALL PROVIDE A MINIMUM CLEARANCE OF EIGHTEEN INCHES (18") BETWEEN THE OUTER SURFACE OF THE STRUCTURE AND THE EXCAVATION OR SHEETING.

- WHEREVER FOUNDATION MATERIAL IS UNSUITABLE, IT SHALL BE EXCAVATED UNTIL A STABLE FOUNDATION IS ACHIEVED. GRANULAR MATERIAL #67 STONE PER ASTM C 12, SHALL THEN BE PLACED IN SIX INCH (6") LAYERS AND COMPACTED UNTIL THE TRENCH BOTTOM HAS BEEN STABILIZED. STANDARD GRANULAR PIPE BEDDING MATERIAL SHALL BE PLACED IN ACCORDANCE WITH ASTM D 2321 FOR PVC PIPE AND ASTM C 12 FOR DIP.

- ALL GRAVITY SEWER MAINS, SERVICE LATERALS AND FORCE MAINS SHALL HAVE A MINIMUM COVER OF THREE FEET (3') AS MEASURED FROM TOP OF PIPE TO FINISH GRADE. THE BPG, INC. ENGINEER MAY REQUIRE ADDITIONAL COVER AS NEEDED FOR PIPE PROTECTION. SEWERS, WHICH HAVE A DEPTH OF COVER LESS THAN THREE FEET (3'), SHALL BE APPROVED AND INSTALLED AS PER BPG, INC. ENGINEER'S WRITTEN INSTRUCTIONS.

- PIPE SHALL BE LAID TRUE TO LINE AND GRADE WITH BELLS UPSTREAM AND SHALL BE LAID TRUE TO LINE AND GRADE WITH SPUDS DOWNSTREAM. THE WATER MAIN LOCATED AT ONE SIDE ON A BENCH OF UNDISTURBED EARTH, AND WITH THE ELEVATION OF THE BOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT 18 INCH VERTICAL SEPARATION--IN WHICH CASE BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF THE SAME MATERIAL AND WITH JOINTS THAT ARE EQUAL TO THE WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING.

- CROSSING A WATER MAIN UNDER A SEWER. WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS UNDER A SEWER, BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF THE SAME MATERIAL AND WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING. A SECTION OF WATER MAIN PIPE SHALL BE CENTERED AT THE POINT OF CROSSING.

- CROSSING A WATER MAIN UNDER A SEWER. WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS UNDER A SEWER, BOTH THE WATER MAIN AND SEWER SHALL BE CONSTRUCTED OF THE SAME MATERIAL AND WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING. A SECTION OF WATER MAIN PIPE SHALL BE CENTERED AT THE POINT OF CROSSING.

## WATER CROSSING SEWER DETAIL

- PRIOR TO COMMENCEMENT OF ANY WORK WITHIN EASEMENTS OR RIGHTS-OF-WAYS THE CONTRACTOR IS REQUIRED TO NOTIFY CONCERNED UTILITY COMPANIES IN ACCORDANCE WITH GS 87-102. CONTRACTOR SHALL VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION. NO SEPARATE PAYMENT. EXISTING UTILITIES SHOWN ARE TAKEN FROM MAPS FURNISHED BY VARIOUS UTILITY COMPANIES AND HAVE NOT BEEN PHYSICALLY LOCATED (I.E. TELEPHONE, GAS, CABLE, ETC.).

- THE CONTRACTOR SHALL DIG UP EACH UTILITY WHICH MAY CONFLICT WITH CONSTRUCTION 14 DAYS IN ADVANCE TO VERIFY LOCATIONS (HORIZONTALLY AND VERTICALLY) TO ALLOW THE ENGINEER AN OPPORTUNITY TO ADJUST THE DESIGN TO AVOID CONFLICTS (NO SEPARATE PAYMENT).

- ALL SANITARY SEWER & WATER CONSTRUCTION SHALL BE IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS OF THE NCDENR-DWQ & NCDENR-PWS. STORM DRAINAGE, STREET CONSTRUCTION AND PAVING SHALL BE IN ACCORDANCE WITH THE N.C.D.O.T.

- UTILITY SERVICES TO INDIVIDUAL PROPERTIES ARE NOT SHOWN IN THE PROFILES FOR SIMPLICITY OF THE DRAWINGS. SERVICES MAY INCLUDE WATER LATERALS, TELEPHONE, ELECTRIC, CABLE, GAS, ETC.

- CONTRACTOR SHALL COORDINATE WITH UTILITY OWNER AND BE RESPONSIBLE FOR TEMPORARY RELOCATION AND/OR SECURING EXISTING UTILITY POLES AND SIGNS AND/OR UTILITIES IN ACCORDANCE WITH UTILITY OWNER REQUIREMENTS DURING THE UTILITY MAIN INSTALLATION AND STREET CONSTRUCTION. (NO SEPARATE PAYMENT).

- BACKFILL SHALL BEGIN AT THE TOP OF THE STANDARD GRANULAR BEDDING AND SHALL BE PLACED IN SIX INCH (6") LAYERS FOR THE INITIAL ONE FOOT OVER THE PIPE AND SHALL BE THOROUGHLY TAMPED TO NINETY-FIVE PERCENT (95%) OF THE MAXIMUM THEORETICAL COMPACTION DENSITY AS DETERMINED BY A STANDARD PROCTOR ON THE MATERIAL. REMAINDER OF THE BACKFILL SHALL BE IN TWO FOOT (2") LAYERS PROPERLY TAMPED.

- COMPLETION: BEFORE CONNECTING TO AN ACTIVE SYSTEM, THE LEAKAGE TESTS SHALL PROMPTLY FOLLOW INSTALLATION OF WASTEWATER PIPE, INCLUDING SERVICES AND KEPT WITHIN A MAXIMUM OF 1000 FEET BEHIND THE WASTEWATER PIPE LAYING OPERATION.


- CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORTS FOR UTILITY CROSSINGS AND REPAIR DAMAGES DUE TO CONSTRUCTION TO THE SATISFACTION OF THE UTILITY INVOLVED AT NO ADDITIONAL EXPENSE TO THE OWNER. UNDERGROUND ELECTRICAL CROSSINGS SHALL BE CROSSED IN ACCORDANCE WITH THE NEC AND TECHNICAL SPECIFICATION SECTION UNDERGROUND ELECTRICAL CROSSING.

- WHERE DEEMED NECESSARY BY THE ENGINEER THAT A SUBSURFACE DRAINAGE SYSTEM IS REQUIRED, THE CONTRACTOR SHALL PROVIDE ALL MATERIALS, TOOLS, LABOR, EQUIPMENT, TIE-UPS TO EXISTING DRAINAGE STRUCTURES AND ALL OTHER INCIDENTALS NECESSARY TO PROVIDE COMPLETE INSTALLATION IN ACCORDANCE WITH CITY OF FAYETTEVILLE STANDARDS. IMPROPERLY INSTALLED AND NON-FUNCTIONING DRAINAGE SHALL BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE. EXISTING FRENCH DRAINAGE DAMAGED DURING CONSTRUCTION SHALL BE REPLACED AND OR REPAIRED AT NO ADDITIONAL EXPENSE TO THE OWNER.

- ANY DRIVEWAY CULVERTS DAMAGED DURING CONSTRUCTION SHALL BE EITHER REPAIRED OR PLACED AT CONTRACTOR'S EXPENSE. FILTER FABRIC CLOTH SHALL BE PLACED OVER EITHER CULVERT ENDS DURING THE COURSE OF CONSTRUCTION. ALL EX. DRAINAGE INFRASTRUCTURE WILL BE RETURNED TO PRE-EXISTING CONDITIONS PRIOR TO FINAL PROJECT APPROVALS.

- ONCE ACCEPTANCE AND START OF THE COLLECTION SYSTEM HAS BEEN RECEIVED, THE CONTRACTOR SHALL PROCEED WITH THE ABANDONMENT PROCEDURES OF THE EXISTING WASTEWATER COLLECTION SYSTEM AS DESCRIBED HEREON.

- THE NOTES CONTAINED HEREIN ARE INTENDED TO SUPPLEMENT THE TECHNICAL SPECIFICATIONS AND PROVIDE EASY REFERENCE FOR THE CONTRACTOR. IN NO CASE SHALL THESE NOTES VOID ANY PART, SECTION OR REQUIREMENT OUTLINED IN THE TECHNICAL SPECIFICATIONS CONTAINED IN THE CONTRACT DOCUMENTS.



## CONCRETE CRADLE CROSSING DETAIL

NOT TO SCALE LOCATIONS AS NOTED ON PLAN

- BRING GRADE TO SPRING LINE FOR PIPE
- EXCAVATE TRENCH AS SHOWN AND PLACE PIPE ON SUPPORTS
- 3



# CONTROL PLAN & SEQUENCE

CONSTRUCTION DRAWINGS  
OWNERSHIP CURRITUCK COUNTY NOR


A circular professional seal. The outer ring contains the text "PROFESSIONAL SEAL" at the top and "DAVID M. KLEBITZ" at the bottom. The inner circle contains "2-26-88" at the top and "ENGINEER" at the bottom. A large, thick black "X" is drawn across the center of the seal.


22	SCALE: 1" = 10
G	CHECKED: MSB
OMK	APPROVED: BPG

OF 35

E:  
65100PH2

CT NO:  
4651





**BISSELL PROFESSIONAL GROUP**  
Bissell Professional Group  
P.O. Box 1068  
352 North Carolina Highway  
Cary, NC 27513  
(919) 261-2256  
FAX (919) 261-1760

Engineers, Planners, Surveyors  
and Environmental Specialists

**PHASE 3**

**SEDIMENTATION AND EROSION CONTROL NOTES**

1. THESE NOTES ARE IN ADDITION TO THE SEDIMENTATION AND EROSION CONTROL NOTES AND DETAILS PROVIDED ON SHEETS 14, 15 & 16.

2. ALL MATERIALS EXCAVATED OVER THE COURSE OF CONSTRUCTION SHALL REMAIN ON THE PROJECT SITE. THIS MATERIAL SHALL BE USED FOR FILLING EXISTING DITCHES, CONSTRUCTION OF ROADWAYS AND PREPARING BUILDING SIDES AS ILLUSTRATED ON THE GRADING PLANS. IF NECESSARY, EXCAVATED MATERIALS REMAINING AT THE END OF CONSTRUCTION MAY BE DISPOSED OF OFF-SITE AT AN APPROVED AND PERMITTED BORROW PIT.

3. OFF-SITE BORROW, IF NECESSARY, MUST BE OBTAINED FROM AN APPROVED AND PERMITTED BORROW PIT OR LAND DISTURBANCE. MATERIAL FOR THIS PROJECT MAY BE OBTAINED FROM PONDS BEING CONSTRUCTED IN THE ADJOINING FLORA FARM PROJECT. PROJECT ID: CURR-2022-018.

4. THIS PROJECT IS ANTICIPATED TO BE CONSTRUCTED IN A SINGLE PHASE.

5. LAND SHALL NOT BE DISTURBED OUTSIDE OF THE LIMITS OF DISTURBANCE SHOWN. CONSTRUCTION AND STABILIZATION ACTIVITIES SHALL, TO THE MAXIMUM EXTENT PRACTICABLE, BE SCHEDULED ACCORDINGLY.

6. THE FOLLOWING PROVIDES AN ESTIMATED MATERIAL BALANCE OF THIS PHASE OF THE PROJECT.

APPROXIMATE CUT VOLUME: 125 CY<sup>4</sup>

APPROXIMATE FILL VOLUME: 7,950 CY<sup>4</sup>

(SEE NOTE ON MATERIAL BALANCE SOURCES)

\*THESE ARE GROSS ESTIMATES AND ARE PROVIDED FOR PERMITTING PURPOSES ONLY. COMPACTION AND SUITABILITY OF SOILS FOR USE IN CONSTRUCTION ARE NOT CONSIDERED AND ADDITIONAL MATERIAL MAY BE NECESSARY. CONTRACTORS SHALL NOT RELY UPON THESE ESTIMATES AND SHOULD DETERMINE THEIR OWN MATERIAL NEEDED FOR CONSTRUCTION.

**CONSTRUCTION SEQUENCE**

1. INSTALL CONSTRUCTION ENTRANCE AT LOCATION SPECIFIED ON PLAN. IF ALTERNATE ACCESS POINTS ARE UTILIZED, A CONSTRUCTION ENTRANCE MUST BE INSTALLED AT THOSE LOCATIONS AS WELL.
2. INSTALL SILT FENCE WHERE SPECIFIED.
3. CONDUCT GENERAL CONSTRUCTION ACTIVITIES FOR INSTALLATION OF PROPOSED ROADWAY, DRAINAGE AND UTILITY IMPROVEMENTS.
4. INSTALL INLET PROTECTION AROUND CATCH BASINS AS INSTALLED.
5. DURING THE COURSE OF CONSTRUCTION, MAINTAIN SILT FENCE, INLET PROTECTION AND ANY ADDITIONAL PROTECTION MEASURES AS NECESSARY AND WHERE NOTED.
6. PERMANENTLY SEED AND STABILIZED ALL DISTURBED AREAS.
7. AFTER STABILIZATION IS ESTABLISHED, REMOVE ALL TEMPORARY EROSION CONTROL MEASURES, CLEAN OUT AND RETURN PONDS TO DESIGN CONDITIONS AND SEED & STABILIZE THOSE AREAS.

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025

2025